Occupational Safety and Health Standards Board

Public and Business Meeting

Meeting Agenda

Prepared by the Department of Industrial Relations
Available on the DIR web page: Standards Board (OSHSB) 2025 Meeting Schedule

OCCUPATIONAL SAFETY
AND HEALTH STANDARDS BOARD
2520 Venture Oaks Way, Suite 350
Sacramento, CA 95833
(916) 274-5721
www.dir.ca.gov/oshsb

MISSION STATEMENT

The mission of the Occupational Safety and Health Standards Board is to promote, adopt, and maintain reasonable and enforceable standards that will ensure a safe and healthy workplace for California workers.

AGENDA

OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD MEETING

PLEASE NOTE: In accordance with section 11123 of the Government Code, Board members as well as members of the public may elect to participate via videoconference.

February 19, 2026
10:00 a.m.

In-Person:

Hotel Katerina
Tack Room
1930 Baney Lane
Chico, CA 95928

Videoconference:

1. Go to https://tkoworks.zoom.us/j/87501250331
2. Enter Webinar ID: 875 0125 0331
3. Join the meeting through the Zoom application OR through your web browser
4. Videoconference will be opened to the public at 9:50 a.m.

Teleconference:

1. Dial 1 (669) 444-9171
2. Enter Webinar ID: 875 0125 0331 and follow the prompts
3. Teleconference will be opened to the public at 9:50 a.m.

Live video stream and audio stream (English and Spanish):

1. Go to https://videobookcase.com/california/oshsb/
2. Video stream and audio stream will launch as the meeting starts at 10:00 a.m.

Public Comment Queue:
If attending the Occupational Safety and Health Standards Board (Board) meeting in person, you will be added to the public comment queue upon completing a comment card on the day of the meeting.

If attending the meeting remotely and you wish to comment on agenda items, you may submit a request to be added to the public comment queue either in advance of or during the meeting through one of the following methods:

ONLINE: Provide your information through the online comment queue portal at https://videobookcase.org/oshsb/public-comment-queue-form/

PHONE: Call **(510) 868-2730** to access the automated comment queue voicemail and provide†: 1) your name as you would like it listed; 2) your affiliation or organization; and 3) the topic you would like to comment on.

† Information requested is voluntary and not required to address the Board.

I. CALL TO ORDER AND INTRODUCTIONS

A. Spanish translation instructions

II. REMARKS FROM THE CHAIR

III. PRESENTATIONS

A. Update on Z308.1 Workplace First Aid Kit Standard Revision: Worker Safety Benefits of the ANSI/ISEA Z308.1-2026 Standard

Dan Glucksman, Senior Director for Policy

International Safety Equipment Association

Diana Jones, Senior Director for Technical Services

International Safety Equipment Association (ISEA)

- Public Comment
- Board Member Comments and Questions

B. Requiring Voice-Activated Room Alerts to Address Staffing Constraints and Remote Scanning Emergencies

Steve Soderholm BSBE, MSME, MRI Engineer / Employee

Tobias Gilk, Architect and Radiology / MRI Safety Expert, MRI safety trainer and consultant for healthcare providers and industry.

Emanuel Kanal, MD, FACR, FISMRM, AANG, Professor of Radiology and Neuroradiology, Director, MR Education, Director of Magnetic Resonance (MR) Services

- Public Comment
- Board Member Comments and Questions

C. Stone Fabrication Industry Overview and Cambria's Experience with Safe Fabrication of Natural Quartz Substances

Rebecca Shult, Chief Legal Officer, Cambria

Marshall Engstrom, Industrial Hygienist, Cambria

- Public Comment
- Board Member Comments and Questions

IV. BUSINESS MEETING

Note: The purpose of the Business Meeting is for the Board to conduct its monthly business. All matters on this agenda are subject to discussion and action as determined to be appropriate by the Board Chair.

For items A and C below, public comment will be limited to two minutes per speaker or four minutes for speakers requiring concurrent English translation.

A. LETTER TO DISTRICT ATTORNEYS REGARDING SILICA

- Public Comment
- Board Member Comments and Questions

B. PROPOSED VARIANCE DECISIONS FOR ADOPTION

- Consent Calendar
- Vote on consent calendar

C. REPORTS

- Executive Officer's Report
- Legislative Update
- Cal/OSHA Report
- State Response Subcommittee Report

D. PUBLIC COMMENT ON NON-AGENDA ITEMS OR TO PROPOSE NEW OR REVISED STANDARDS

This portion of the meeting is open to any interested person proposing new or revised standards to the Board or commenting on occupational safety and health issues (Labor Code section 142.2) not on the agenda. The Board is prohibited to act on items that are not noticed on the agenda but may refer items to staff for future consideration.

Public comment will be limited to two minutes per speaker or four minutes for speakers requiring concurrent English translation.

The Board encourages comments on occupational safety and health matters not included on the monthly agenda. If you have a comment and cannot attend during the non-agenda comment period, OSHSB staff will do their best to read emailed comments into the record. Please send your non-agenda comment to oshsb_nacomments@dir.ca.gov by 5:00 PM the day prior to the meeting. Your comment should be clear, concise and 500 words or less.

Any individual or group wanting to make a presentation during the Public Meeting should visit https://www.dir.ca.gov/oshsb/presentations-for-oshsb.html for further information.

E. COMMENTS BY BOARD MEMBERS

Any Board member may identify a topic of interest during the Board meeting. However, the Board may not substantially discuss or act on any matter raised during the meeting that is not included on this agenda, except to decide to place the matter on the agenda of a future meeting. (GC sections 11125 & 11125.7(a).).

F. CLOSED SESSION

- Public comment on Closed Session Agenda Items

Pending Decisions

- Permanent Variance No. 20-V-096 (Tutor Perini/O&G JV)
- Permanent Variance No. 23-V-580 (Dragados)
- Permanent Variance No. 20-V-300 (Pepsi Bottling Group, LLC)

Personnel

G. RETURN TO OPEN SESSION

- Report from closed session

H. ADJOURNMENT OF THE MEETING

Next Meeting: March 19, 2026
City of Palm Springs
Council Chambers
3200 E. Tahquitz Canyon Way
Palm Springs, CA 92262
10:00 a.m.

CLOSED SESSION

- If necessary, consideration of personnel matters. (GC section 11126(a)(1)).
- If necessary, consideration of pending litigation pursuant to GC section 11126(e)(1).
- If necessary, to deliberate on a pending decision. (GC section 11126(c)(3)).

PUBLIC COMMENT

Public Hearing
During the Public Hearing, members of the public may provide comments regarding standards that have been noticed to the public for a 45-day comment period. An individual wishing to comment must complete a speaker comment card. Efforts will be made to accommodate everyone who signs up to speak. However, given time constraints, there is no guarantee that all who have signed up will be able to address the Board.

Each individual who submits a comment card will get up to two minutes to speak. The Board Chair may extend the speaking time allotted when practical. The total time for public comment is 120 minutes unless extended by the Board Chair.

Business Meeting Non-Agendized
During the Business Meeting Non-Agendized, members of the public can address the Board on items of interest that are within the Board's jurisdiction but are not on the noticed agenda. The Board is not permitted to take action on items that are not on the noticed agenda but may refer items to staff for future consideration. The Board reserves the right to limit the time for speakers.

DISABILITY ACCOMMODATION NOTICE

Under Government Code section 11123(a), all meetings of a state body are open and public, and all persons are permitted to attend any meeting of a state body, except as otherwise provided in the Bagley-Keene Open Meeting Act.

If disability-related modifications or accommodations are required to participate in the meeting, please contact the Diversity and Inclusion Office at DIO@DIR.CA.GOV. To ensure the availability of your requested accommodation, please submit your request at least 10 days in advance.

Please contact the California Relay Service by dialing 711 or (800) 735-2929 (TTY) or (800) 855-3000 (TTY-Spanish).

TRANSLATION

Requests for translation services should be made no later than five (5) days before the meeting. Request may be made to by email to oshsb@dir.ca.gov.

Occupational Safety and Health Standards Board

Public and Business Meeting

Meeting Notice

Prepared by the Department of Industrial Relations
Available on the DIR web page: Standards Board (OSHSB) 2025 Meeting Schedule

OCCUPATIONAL SAFETY
AND HEALTH STANDARDS BOARD
2520 Venture Oaks Way, Suite 350
Sacramento, CA 95833
(916) 274-5721
Website address www.dir.ca.gov/oshsb

NOTICE OF PUBLIC MEETING AND BUSINESS MEETING OF THE OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD

Pursuant to Government Code section 11346.4 and the provisions of Labor Code Sections 142.1, 142.2, 142.3, 142.4, and 144.6, the Occupational Safety and Health Standards Board ("Board") of the State of California has set the time and place for a Public Meeting and Business Meeting:

QR Code for Access:

On **February 19, 2026**, at 10:00 a.m.
Hotel Katerina
Tack Room
1930 Baney Lane
Chico, California 95928

as well as via the following:

- Videoconference at https://tkoworks.zoom.us/j/87501250331
- Teleconference at (669) 444-9171 (Webinar ID 875 0125 0331)
- Live video stream and audio stream (English and Spanish) at: https://videobookcase.com/california/oshsb/

At the Public Meeting, the Board will make time available to receive comments or proposals from interested persons on any item concerning occupational safety and health.

At the Business Meeting, the Board will conduct its monthly business.

DISABILITY ACCOMMODATION NOTICE: Disability accommodation is available upon request. Any person with a disability requiring an accommodation, auxiliary aid or service, or a modification of policies or procedures to ensure effective communication and access to the public hearings/meetings of the Board should contact the Disability Accommodation Coordinator at (916) 274-5721 or the state-wide Disability Accommodation Coordinator at 1 (866) 326-1616 (toll free). The state-wide Coordinator can also be reached through the California Relay Service, by dialing 711 or 1 (800) 735-2929 (TTY) or 1 (800) 855-3000 (TTY-Spanish).

Accommodations can include modifications of policies or procedures or provision of auxiliary aids or services. Accommodations include, but are not limited to, an Assistive Listening System (ALS), a Computer-Aided Transcription System or Communication Access Realtime Translation (CART), a sign-language interpreter, documents in Braille, large print or on computer disk, and audio cassette recording. Accommodation requests should be made as soon as possible. Requests for an ALS or CART should be made no later than five (5) days before the hearing.

OCCUPATIONAL SAFETY AND HEALTH
STANDARDS BOARD

JOSEPH M. ALIOTO JR., Chairman

Occupational Safety and Health Standards Board

Business Meeting Proposed Variance Decisions

Prepared by the Department of Industrial Relations
Available on the DIR web page: Standards Board (OSHSB) 2025 Meeting Schedule

CONSENT CALENDAR—PROPOSED VARIANCE DECISIONS
FEBRUARY 19, 2026, MONTHLY BUSINESS MEETING
OF THE OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD

PROPOSED DECISIONS FOR BOARD CONSIDERATION, HEARD ON JANUARY 21, 2026

Docket Number	Applicant Name	Safety Order(s) at Issue	Proposed Decision Recommendation
1. 14-V-295M1	Mountain JD, LLC	ELEVATOR	GRANT
2. 21-V-665M1	Google LLC	ELEVATOR	GRANT
3. 22-V-635M1	The Leon S. Kaplan Revocable Trust – Leon S. Kaplan Trustee	ELEVATOR	GRANT
4. 23-V-054M1	Burbank Boyz II, LLC	ELEVATOR	GRANT
5. 23-V-157M1	San Ysidro Health National City Dev. Corp	ELEVATOR	GRANT
6. 23-V-337M1	Kettner Crossing LP	ELEVATOR	GRANT
7. 23-V-563M1	Phoenix 801 Pine LP	ELEVATOR	GRANT
8. 24-V-566M1	Jefferson Ocean Creek, LLC	ELEVATOR	GRANT
9. 25-V-073M1	Mountain House Apartments Phase II Owner, LLC	ELEVATOR	GRANT
10. 25-V-117M1	Domeyko Taylor RE 1, LLC	ELEVATOR	GRANT
11. 25-V-339	CMH San Diego LLC	ELEVATOR	GRANT
12. 25-V-451	SSF Battery Point LP	ELEVATOR	GRANT
13. 25-V-452	Group One Integrity, Rosemont, LLC	ELEVATOR	GRANT
14. 25-V-453	IDEC Corporation	ELEVATOR	GRANT
15. 25-V-454	ISF Ativo Santa Clarita LLC	ELEVATOR	GRANT
16. 25-V-455	Lincoln Beach LP	ELEVATOR	GRANT
17. 25-V-456	Long Beach Community College District	ELEVATOR	GRANT
18. 25-V-457	Montrose Street, LLC	ELEVATOR	GRANT
19. 25-V-458	Oakland Pacific Associates II, A California Limited Partnership	ELEVATOR	GRANT

Docket Number	Applicant Name	Safety Order(s) at Issue	Proposed Decision Recommendation
20. 25-V-459	Or Hachaim Academy	ELEVATOR	GRANT
21. 25-V-460	Rose Hill Courts II Housing Partners, L.P.	ELEVATOR	GRANT
22. 25-V-462	Compton College	ELEVATOR	GRANT
23. 25-V-463	Daley Center Drive Associates LLC, A Delaware Limited Company	ELEVATOR	GRANT
24. 25-V-464	Nueva Day School	ELEVATOR	GRANT
25. 25-V-465	The Grant at Mission Trails LP	ELEVATOR	GRANT
26. 25-V-466	UC Madera Owner LLC	ELEVATOR	GRANT
27. 25-V-468	The Broad	ELEVATOR	GRANT
28. 25-V-469	Victoria Gardens Investor, LLC	ELEVATOR	GRANT
29. 25-V-471	11250 La Grange LLC	ELEVATOR	GRANT
30. 25-V-474	HIW Associates, LP	ELEVATOR	GRANT
31. 25-V-475	Liberty Homes, LLC	ELEVATOR	GRANT
32. 25-V-476	Pacific Square San Gabriel, LLC	ELEVATOR	GRANT
33. 25-V-477	Pacific Square San Gabriel, LLC	ELEVATOR	GRANT
34. 25-V-478	Regional Street Investors, L.P.	ELEVATOR	GRANT
35. 25-V-479	Santa Barbara Neighborhood Clinics	ELEVATOR	GRANT
36. 25-V-480	State of California	ELEVATOR	GRANT
37. 25-V-481	The Trails at CMR CIC, LP	ELEVATOR	GRANT
38. 25-V-482	The Trails at CMR CIC, LP	ELEVATOR	GRANT
39. 25-V-483	University of California Santa Barbara	ELEVATOR	GRANT
40. 25-V-484	University of California Santa Barbara	ELEVATOR	GRANT
41. 25-V-485	University of California Santa Barbara	ELEVATOR	GRANT
42. 25-V-486	USS Trafalgar LLC	ELEVATOR	GRANT
43. 25-V-487	DBC III SPE LLC	ELEVATOR	GRANT

Docket Number	Applicant Name	Safety Order(s) at Issue	Proposed Decision Recommendation
44. 25-V-488	Phoenix 810 Pine LP	ELEVATOR	GRANT
45. 25-V-491	UC Davis Health	ELEVATOR	GRANT
46. 25-V-492	The Open Door Network	ELEVATOR	GRANT
47. 25-V-493	Perris Elementary School District	ELEVATOR	GRANT
48. 25-V-494	Manteca Unified School District	ELEVATOR	GRANT
49. 25-V-495	RAR2-DEL AMO CROSSING OWNER, LLC	ELEVATOR	GRANT
50. 25-V-496	Meridian Family Apartments, L.P.	ELEVATOR	GRANT
51. 25-V-498	The Hamid and Azita Yousefian Family Trust	ELEVATOR	GRANT
52. 25-V-499	3636 4th Ave LLC.	ELEVATOR	GRANT
53. 25-V-500	Lawndale Elementary School District	ELEVATOR	GRANT
54. 25-V-501	Liberation Park Residences, L.P.	ELEVATOR	GRANT
55. 25-V-502	160 Freelon Housing Partners, L.P.	ELEVATOR	GRANT
56. 25-V-503	1634 20th Street, L.P.	ELEVATOR	GRANT
57. 25-V-504	Berendo QOZB LLC	ELEVATOR	GRANT
58. 25-V-505	BIF NON OZ 6200 Broadway BLK, LLC	ELEVATOR	GRANT
59. 25-V-506	Christ Presbyterian Church	ELEVATOR	GRANT
60. 25-V-507	City of Ontario	ELEVATOR	GRANT
61. 25-V-508	CoreLink-Scripps Holdings, LLC	ELEVATOR	GRANT
62. 25-V-509	CoreLink-Scripps Holdings, LLC	ELEVATOR	GRANT
63. 25-V-510	California State University San Marcos	ELEVATOR	GRANT
64. 25-V-511	Formosa Bureau of Investments LLC.	ELEVATOR	GRANT
65. 25-V-512	Hope Apartments Owner, LLC,	ELEVATOR	GRANT
66. 25-V-513	LINC-Eureka APTS, LP	ELEVATOR	GRANT
67. 25-V-514	LINC-Eureka APTS, LP	ELEVATOR	GRANT

Docket Number	Applicant Name	Safety Order(s) at Issue	Proposed Decision Recommendation
68. 25-V-515	LINC-Eureka APTS, LP	ELEVATOR	GRANT
69. 25-V-516	Marin County Pacific Associates LP	ELEVATOR	GRANT
70. 25-V-517	Millbrae Broadway Pacific Associates, LP, A California Limited Partnership	ELEVATOR	GRANT
71. 25-V-518	QND LLC	ELEVATOR	GRANT
72. 25-V-519	Richman Oroville Senior Apartments, LP	ELEVATOR	GRANT
73. 25-V-520	Rise Carmel LP	ELEVATOR	GRANT
74. 25-V-521	Sacramento 11th Street II, LP	ELEVATOR	GRANT
75. 25-V-522	San Jose South 1st Street Associates, a California Limited Partnership	ELEVATOR	GRANT
76. 25-V-523	San Francisco Airport	ELEVATOR	GRANT
77. 25-V-524	Street Retail, LLC	ELEVATOR	GRANT
78. 25-V-525	Street Retail, LLC	ELEVATOR	GRANT
79. 25-V-526	SyRes Properties LLC	ELEVATOR	GRANT
80. 25-V-528	Venice Cardiff, LLC	ELEVATOR	GRANT
81. 25-V-529	Ventura Surgical, LLC	ELEVATOR	GRANT
82. 25-V-530	Icon SSF Apartments Owner LLC	ELEVATOR	GRANT
83. 25-V-531	County of Orange	ELEVATOR	GRANT
84. 25-V-532	JS IV View at San Bruno, LLC	ELEVATOR	GRANT
85. 25-V-533	JS IV View at San Bruno, LLC	ELEVATOR	GRANT
86. 25-V-534	Lone Oak – Rancho, L.L.C.	ELEVATOR	GRANT
87. 25-V-535	Lone Oak – Rancho, L.L.C.	ELEVATOR	GRANT
88. 26-V-001	SHP Castro LLC	ELEVATOR	GRANT

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application to Modify Permanent Variance by: Mountain JD, LLC	Permanent Variance No: 14-V-295M1 **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The following person or entity ("Applicant") has applied for a modification of permanent variance from a provision of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Preexisting Permanent Variance No.	Preexisting Applicant Name	Preexisting Variance Address of Record
14-V-295	BIT Holdings Sixty-Eight Inc.	101 North Almaden Avenue, San Jose, CA

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference, by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, Kristina Nguyen appeared as the Applicant; and Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application for Modification of Permanent Variance
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the safety regulation requirements from which variance shall issue. On January 21, 2026, the

hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. The Applicant requests modification of the address of the unchanging variance location specified within Board records for each conveyance the subject of previously granted Permanent Variance No. 14-V-295 and any previously granted modifications therewith.
2. The Application declared to be wholly truthful under penalty of perjury by Application signatory, states facts upon which reasonably may be based a finding that the address, specified in the records of the Board, at which Permanent Variance No. 14-V-295M1 is in effect, in fact is more completely, and correctly the different combination of addresses specified in below subsection D.1.
3. The Applicant also requests modification of the permanent variance to indicate the employer/owner of the conveyance(s) as Mountain JD, LLC.
4. The Application declared to be wholly truthful under penalty of perjury by Application signatory, states facts upon which reasonably may be based a finding that the owner, specified in the records of the Board, at which Permanent Variance No. 14-V-295M1 is in effect, in fact is more completely, and correctly specified in below subsection D.1.
5. Cal/OSHA has evaluated the request for modification of variance location address, finds no issue with it, and recommends that the application for modification be granted subject to the same conditions of the Decision and Order in Permanent Variance No. 14-V-295 and any previously granted modifications therewith.
6. The Board finds the above subpart C.2 and C4 referenced declaration to be credible, uncontroverted, and consistent with available, sufficient facts, and of no bearing as to the finding of equivalent occupational health and safety upon which Grant of preexisting Permanent Variance 14-V-295 and any previously granted modifications therewith was based.
7. The Board finds the correct address by which to designate the location of each conveyance the subject of Permanent Variance No. 14-V-295, to be:

   77 N. Almaden Ave.
   San Jose, CA

8. The Board finds the correct owner of each conveyance the subject of Permanent Variance No. 14-V-295, to be:

   Mountain JD, LLC.

D. Decision and Order

1. Permanent Variance Application No. 14-V-295M1 is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 14-V-295 and any previously granted modifications therewith, shall have the following address designation:

   77 N. Almaden Ave.
   San Jose, CA

2. Permanent Variance Application No. 14-V-295M1 is conditionally GRANTED, thereby modifying Board records, such that the owner of each conveyance being the subject of Permanent Variance No. 14-V-295 and any previously granted modifications therein, is:

Mountain JD, LLC.

3. Permanent Variance No. 14-V-295 and any previously granted modifications therewith, being only modified as to the subject location address and owner specified in above Decision and Order section 1 and 2, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into this Decision and Order of Permanent Variance No. 14-V-295M1.

4. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.

5. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 27, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application to Modify Permanent Variance by: Google LLC	OSHSB File No.: 21-V-665M1 **PROPOSED DECISION** Hearing Date: January 21, 2026

A. Subject Matter

1. The following person or entity ("Applicant") has applied for a modification of permanent variance from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations, for each elevator having the below specified preexisting variance location address of record:

Preexisting OSHSB File No.	Applicant Name	Preexisting Elevator Identification Number
21-V-665	Google LLC	2B

2. The safety order requirements are set out within section 3141 incorporated ASME A17.1-2004, sections 2.18.5.1 and 2.20.4.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference, by the Occupational Safety and Health Standards Board ("Board"), with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit, in accordance with section 426.

2. At the hearing, Fuei Saetern, with KONE, Inc., appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD-1	Application(s) for Modification of Permanent Variance
PD-2	OSHSB Notice of Hearing
PD-3	Cal/OSHA Review of Variance Modification Application
PD-4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. The Applicant requests modification as to the identification number of the elevator being the subject of previously granted Permanent Variance No. 21-V-665 from being designated as elevator 2B to elevator 1B.

2. Cal/OSHA has evaluated the request, finds no issue with it, and recommends that the application for modification be granted subject to the same conditions of the Decision and Order in OSHSB Permanent Variance File No. 21-V-665.

D. Decision and Order

1. Application for Modification of Permanent Variance, No. 21-V-665M1, is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, the identification number of elevator 2B shall instead be elevator 1B.

2. Permanent Variance No. 21-V-665, being only modified as to the identification number of elevator 2B to elevator 1B, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into Modification of Permanent Variance 21-V-665M1.

3. The applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way that the Applicant was required to notify them of the application for permanent variance, sections 411.2 and 411.3.

4. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed for its issuance.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption

Kelly Chau, Hearing Officer

Dated: January 28, 2026

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application to Modify Permanent Variance by: The Leon S. Kaplan Revocable Trust - Leon S. Kaplan Trustee	Permanent Variance No: 22-V-635M1 **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The following person or entity ("Applicant") has applied for a modification of permanent variance from a provision of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Preexisting Permanent Variance No.	Applicant Name	Preexisting Variance Address of Record
22-V-635	The Leon S. Kaplan Revocable Trust - Leon S. Kaplan Trustee	5314 N. Cartwright Ave. North Hollywood, CA

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference, by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, Fuei Saetern, with KONE INC., appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application for Modification of Permanent Variance
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the

safety regulation requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. The Applicant requests modification of the address of the unchanging variance location specified within Board records for each conveyance the subject of previously granted Permanent Variance No. 22-V-635 and any previously granted modifications therewith.
2. The Application declared to be wholly truthful under penalty of perjury by Application signatory, states facts upon which reasonably may be based a finding that the address, specified in the records of the Board, at which Permanent Variance No. 22-V-635M1 is in effect, in fact is more completely, and correctly the different combination of addresses specified in below subsection D.1.
3. Cal/OSHA has evaluated the request for modification of variance location address, finds no issue with it, and recommends that the application for modification be granted subject to the same conditions of the Decision and Order in Permanent Variance No. 22-V-635 and any previously granted modifications therewith.
4. The Board finds the above subpart C.2 referenced declaration to be credible, uncontroverted, and consistent with available, sufficient facts, and of no bearing as to the finding of equivalent occupational health and safety upon which Grant of preexisting Permanent Variance 22-V-635 and any previously granted modifications therewith was based.
5. The Board finds the correct address by which to designate the location of each conveyance the subject of Permanent Variance No. 22-V-635, to be:

5320 Cartwright Ave.
North Hollywood, CA

D. Decision and Order

1. Permanent Variance Application No. 22-V-635M1 is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 22-V-635 and any previously granted modifications therewith, shall have the following address designation:

5320 Cartwright Ave.
North Hollywood, CA

2. Permanent Variance No. 22-V-635 and any previously granted modifications therewith, being only modified as to the subject location address specified in above Decision and Order section 1, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into this Decision and Order of Permanent Variance No. 22-V-635M1.
3. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
4. This Decision and Order shall remain in effect unless modified or revoked upon application by

the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 28, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application to Modify Permanent Variance by: Burbank Boyz II, LLC	Permanent Variance No: 23-V-054M1 **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The following person or entity ("Applicant") has applied for a modification of permanent variance from a provision of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Preexisting Permanent Variance No.	Applicant Name	Preexisting Variance Address of Record
23-V-054	Burbank Boyz II, LLC	4508 N. Mariota Ave. North Hollywood, CA

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference, by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, Peter Cuellar, with Schindler Elevator Corporation, appeared on behalf of each Applicant; and Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application for Modification of Permanent Variance
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the

safety regulation requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. The Applicant requests modification of the address of the unchanging variance location specified within Board records for each conveyance the subject of previously granted Permanent Variance No. 23-V-054 and any previously granted modifications therewith.
2. The Application declared to be wholly truthful under penalty of perjury by Application signatory, states facts upon which reasonably may be based a finding that the address, specified in the records of the Board, at which Permanent Variance No. 23-V-054M1 is in effect, in fact is more completely, and correctly the different combination of addresses specified in below subsection D.1.
3. Cal/OSHA has evaluated the request for modification of variance location address, finds no issue with it, and recommends that the application for modification be granted subject to the same conditions of the Decision and Order in Permanent Variance No. 23-V-054 and any previously granted modifications therewith.
4. The Board finds the above subpart C.2 referenced declaration to be credible, uncontroverted, and consistent with available, sufficient facts, and of no bearing as to the finding of equivalent occupational health and safety upon which Grant of preexisting Permanent Variance 23-V-054 and any previously granted modifications therewith was based.
5. The Board finds the correct address by which to designate the location of each conveyance the subject of Permanent Variance No. 23-V-054, to be:

10067 Riverside Dr.
Toluca Lake, CA

D. Decision and Order

1. Permanent Variance Application No. 23-V-054M1 is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 23-V-054 and any previously granted modifications therewith, shall have the following address designation:

10067 Riverside Dr.
Toluca Lake, CA

2. Permanent Variance No. 23-V-054 and any previously granted modifications therewith, being only modified as to the subject location address specified in above Decision and Order section 1, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into this Decision and Order of Permanent Variance No. 23-V-054M1.
3. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
4. This Decision and Order shall remain in effect unless modified or revoked upon application by

the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 28, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application to Modify Permanent Variance by: San Ysidro Health National City Dev. Corp	Permanent Variance No: 23-V-157M1 **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The following person or entity ("Applicant") has applied for a modification of permanent variance from a provision of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Preexisting Permanent Variance No.	Applicant Name	Preexisting Variance Address of Record
23-V-157	San Ysidro Health National City Dev. Corp	601 E. 14th St. San Diego, CA

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference, by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application for Modification of Permanent Variance
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the

safety regulation requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. The Applicant requests modification of the address of the unchanging variance location specified within Board records for each conveyance the subject of previously granted Permanent Variance No. 23-V-157 and any previously granted modifications therewith.
2. The Application declared to be wholly truthful under penalty of perjury by Application signatory, states facts upon which reasonably may be based a finding that the address, specified in the records of the Board, at which Permanent Variance No. 23-V-157M1 is in effect, in fact is more completely, and correctly the different combination of addresses specified in below subsection D.1.
3. Cal/OSHA has evaluated the request for modification of variance location address, finds no issue with it, and recommends that the application for modification be granted subject to the same conditions of the Decision and Order in Permanent Variance No. 23-V-157 and any previously granted modifications therewith.
4. The Board finds the above subpart C.2 referenced declaration to be credible, uncontroverted, and consistent with available, sufficient facts, and of no bearing as to the finding of equivalent occupational health and safety upon which Grant of preexisting Permanent Variance 23-V-157 and any previously granted modifications therewith was based.
5. The Board finds the correct address by which to designate the location of each conveyance the subject of Permanent Variance No. 23-V-157, to be:

601 E 14th Street
National City, CA

D. Decision and Order

1. Permanent Variance Application No. 23-V-157M1 is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 23-V-157 and any previously granted modifications therewith, shall have the following address designation:

601 E 14th Street
National City, CA

2. Permanent Variance No. 23-V-157 and any previously granted modifications therewith, being only modified as to the subject location address specified in above Decision and Order section 1, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into this Decision and Order of Permanent Variance No. 23-V-157M1.
3. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
4. This Decision and Order shall remain in effect unless modified or revoked upon application by

the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application to Modify Permanent Variance by: Kettner Crossing LP	Permanent Variance No: 23-V-337M1 **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The following person or entity ("Applicant") has applied for a modification of permanent variance from a provision of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Preexisting Permanent Variance No.	Applicant Name	Preexisting Variance Address of Record
23-V-337	Kettner Crossing LP	1548 Kettner Blvd. San Diego, CA

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference, by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application for Modification of Permanent Variance
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the

safety regulation requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. The Applicant requests modification of the address of the unchanging variance location specified within Board records for each conveyance the subject of previously granted Permanent Variance No. 23-V-337 and any previously granted modifications therewith.
2. The Application declared to be wholly truthful under penalty of perjury by Application signatory, states facts upon which reasonably may be based a finding that the address, specified in the records of the Board, at which Permanent Variance No. 23-V-337M1 is in effect, in fact is more completely, and correctly the different combination of addresses specified in below subsection D.1.
3. Cal/OSHA has evaluated the request for modification of variance location address, finds no issue with it, and recommends that the application for modification be granted subject to the same conditions of the Decision and Order in Permanent Variance No. 23-V-337 and any previously granted modifications therewith.
4. The Board finds the above subpart C.2 referenced declaration to be credible, uncontroverted, and consistent with available, sufficient facts, and of no bearing as to the finding of equivalent occupational health and safety upon which Grant of preexisting Permanent Variance 23-V-337 and any previously granted modifications therewith was based.
5. The Board finds the correct address by which to designate the location of each conveyance the subject of Permanent Variance No. 23-V-337, to be:

1590 Kettner Blvd.
San Diego, CA

D. Decision and Order

1. Permanent Variance Application No. 23-V-337M1 is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 23-V-337 and any previously granted modifications therewith, shall have the following address designation:

1590 Kettner Blvd.
San Diego, CA

2. Permanent Variance No. 23-V-337 and any previously granted modifications therewith, being only modified as to the subject location address specified in above Decision and Order section 1, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into this Decision and Order of Permanent Variance No. 23-V-337M1.
3. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
4. This Decision and Order shall remain in effect unless modified or revoked upon application by

the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application to Modify Permanent Variance by: Phoenix 801 Pine LP	Permanent Variance No: 23-V-563M1 **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The following person or entity ("Applicant") has applied for a modification of permanent variance from a provision of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Preexisting Permanent Variance No.	Applicant Name	Preexisting Variance Address of Record	Preexisting No. of Conveyances
23-V-563	Phoenix 801 Pine LP	801 Pine Street Oakland, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference, by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, Pete Cuellar, with Schindler Elevator Corporation, appeared on behalf of each Applicant; and Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application for Modification of Permanent Variance
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the safety regulation requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. The Applicant requests modification of the address of the unchanging variance location specified within Board records for each conveyance the subject of previously granted Permanent Variance 23-V-563 and any previously granted modifications therewith.
2. The Applicant requests modification of the quantity of conveyances the subject of previously granted Permanent Variance No. 23-V-563, to change the quantity of conveyances from 3 to 2.
3. The modification application submitted by applicant, declared to be wholly truthful under penalty of perjury by the signatory, states facts upon which reasonably may be based a finding that the number of conveyances has changes from 3 to 2 and the address, specified in the records of the Board, at which Permanent Variance No. 23-V-563 is in effect, in fact is more completely, and correctly the different address information specified in below subsection C.6.
4. Cal/OSHA has evaluated the aforementioned request for modification, finds no issue with it, and recommends that the application for modification be granted subject to the same conditions of the Decision and Order in Permanent Variance No. 23-V-563 and any previously granted modifications therewith.
5. The Board finds the declaratory statements of the Applicant signatory to be credible, uncontroverted, and consistent with available, sufficient facts, and of no bearing as to the finding of equivalent occupational health and safety upon which, in substantial part, grant of preexisting Permanent Variance 23-V-563 and any previously granted modifications therewith was based.
6. The Board finds the correct address by which to designate the location of each conveyance the subject of Permanent Variance No. 23-V-563, to be:

821 Pine Street
Oakland, CA

D. Decision and Order

1. Permanent Variance Application No. 23-V-563M1 is conditionally GRANTED, as specified below, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 23-V-563, and any previously granted modifications therewith, shall have the following address designation:

821 Pine Street
Oakland, CA

2. Additionally, the quantity of conveyances is hereby modified such that a total of 2 elevators are the subject of Permanent Variance No. 23-V-563M1.
3. Permanent Variance No(s). 23-V-563 and any previously granted modifications therewith, only being modified as specified in above Decision and Order sections 1 and 2, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into this Decision and Order of Permanent Variance No. 23-V-563M1.

4. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
5. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 28, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application to Modify Permanent Variance by: Jefferson Ocean Creek, LLC	Permanent Variance No: 24-V-566M1 **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The following person or entity ("Applicant") has applied for a modification of permanent variance from a provision of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Preexisting Permanent Variance No.	Applicant Name	Preexisting Variance Address of Record
24-V-566	Jefferson Ocean Creek, LLC	Building 3 - 1939 S. Oceanside Blvd. Oceanside, CA

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference, by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, Fuei Saetern, with KONE INC., appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application for Modification of Permanent Variance
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the safety regulation requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. The Applicant requests modification of the address of the unchanging variance location specified within Board records for each conveyance the subject of previously granted Permanent Variance No. 24-V-566 and any previously granted modifications therewith.
2. The Application declared to be wholly truthful under penalty of perjury by Application signatory, states facts upon which reasonably may be based a finding that the address, specified in the records of the Board, at which Permanent Variance No. 24-V-566M1 is in effect, in fact is more completely, and correctly the different combination of addresses specified in below subsection D.1.
3. Cal/OSHA has evaluated the request for modification of variance location address, finds no issue with it, and recommends that the application for modification be granted subject to the same conditions of the Decision and Order in Permanent Variance No. 24-V-566 and any previously granted modifications therewith.
4. The Board finds the above subpart C.2 referenced declaration to be credible, uncontroverted, and consistent with available, sufficient facts, and of no bearing as to the finding of equivalent occupational health and safety upon which Grant of preexisting Permanent Variance 24-V-566 and any previously granted modifications therewith was based.
5. The Board finds the correct address by which to designate the location of each conveyance the subject of Permanent Variance No. 24-V-566, to be:

1939 S Oceanside Blvd, Bldg #5
Oceanside, CA

D. Decision and Order

1. Permanent Variance Application No. 24-V-566M1 is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 24-V-566 and any previously granted modifications therewith, shall have the following address designation:

1939 S Oceanside Blvd, Bldg #5
Oceanside, CA

2. Permanent Variance No. 24-V-566 and any previously granted modifications therewith, being only modified as to the subject location address specified in above Decision and Order section 1, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into this Decision and Order of Permanent Variance No. 24-V-566M1.
3. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.

4. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 28, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Modification of Permanent Variance by: Mountain House Apartments Phase II Owner, LLC	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicant") below have applied for modification of permanent variance from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulation. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Variance No.	Applicant Name	Variance Location Address	No. of Elevators
25-V-073M1	Mountain House Apartments Phase II Owner, LLC	234 S. Tradition St., Mountain House, CA	1

1. These proceedings are conducted in accordance with Labor Code section 143, and section 401, et seq. of the Occupation Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference by the Board with Hearing Officer, Kelly Chau, presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, James Day with TK Elevator, appeared on behalf of the Applicant. Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD-1	Application(s) for Permanent Variance
PD-2	OSHSB Notice of Hearing
PD-3	Cal/OSHA Review of Variance Application
PD-4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Applicant is requesting to modify the permanent variance decision, specifically the language contained in Permanent Variance No. 25-V-073 Section (E), Decision and Order, Subsection (3), Paragraph (3.1), to include an optional SIL rated TK Elevator model HVI-44 inverter for accommodating power supply conditions, as provided by power company, at the address of record, as follows:

   The SIL rated systems and related circuits shall consist of: the driving-machine motor control system shall consist of a TKE, model HVI-22 ~~HW, High Voltage~~ ***or HVI-44*** *Inverter containing a Safe Torque Off printed circuit board assembly (STO). The STO shall be labeled or marked with a SIL rating (not less than SIL3), the name or mark of the certifying organization and SIL certification number FS/71/220, followed by the applicable revision number (as in FS/71/220/23/1060).*

2. The Applicant asserts that the revisions requested above allow for an alternative inverter device to accommodate lower electrical supply conditions provided by the power company.

3. Cal/OSHA recently reviewed the TK Elevator HVI 44 Inverter for compliance with A17.5 Elevator and Escalator Electrical Equipment certification standards and IEC 61508-2 and IEC 61508-3 SIL Rating Standards. On December 5, 2025, the Elevator Unit issued an amended Acceptance Memorandum affirming compliance with the Elevator Safety Orders CCR Tile 8, Group IV, 3141.3 Static Controls.

4. Cal/OSHA believes that the Applicant's proposal to modify the existing condition provides equivalent safety.

D. Decision and Order

1. Permanent Variance Application No. 25-V-073M1 is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 25-V-073 and any

previously granted modifications therewith, shall have the following edit to (E) Decision and Order, Subsection (3), Paragraph (3.1):

> *The SIL rated systems and related circuits shall consist of: the driving-machine motor control system shall consist of a TKE, model HVI-22 ~~HW, High Voltage~~* ***or HVI-44*** *Inverter containing a Safe Torque Off printed circuit board assembly (STO). The STO shall be labeled or marked with a SIL rating (not less than SIL3), the name or mark of the certifying organization and SIL certification number FS/71/220, followed by the applicable revision number (as in FS/71/220/23/1060).*

2. Permanent Variance No. 25-V-073, being only modified as to include the optional HVI-44 inverter language above, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into Modification of Permanent Variance 25-V-073M1.

3. The applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way that the Applicant was required to notify them of the application for permanent variance, sections 411.2 and 411.3.

4. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed for its issuance.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 27, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Modification of Permanent Variance by: Domeyko Taylor RE 1, LLC	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicant") below have applied for modification of permanent variance from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulation. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Variance No.	Applicant Name	Variance Location Address	No. of Elevators
25-V-117M1	Domeyko Taylor RE 1, LLC	583 F St. Lincoln, CA	1

1. These proceedings are conducted in accordance with Labor Code section 143, and section 401, et seq. of the Occupation Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026, via videoconference by the Board with Hearing Officer, Kelly Chau, presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, James Day with TK Elevator, appeared on behalf of the Applicant. Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD-1	Application(s) for Permanent Variance
PD-2	OSHSB Notice of Hearing
PD-3	Cal/OSHA Review of Variance Application
PD-4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Applicant is requesting to modify the permanent variance decision, specifically the language contained in Permanent Variance No. 25-V-073 Section (E), Decision and Order, Subsection (3), Paragraph (3.1), to include an optional SIL rated TK Elevator model HVI-44 inverter for accommodating power supply conditions, as provided by power company, at the address of record, as follows:

Pursuant to Cal/OSHA review of Permanent Variance Decision and Order, 25-V-117, Cal/OSHA discovered the SIL Certification number in section € Decision and Order, subsection (3), paragraph(3.1) is misrepresented as F/7**4**/220 and requires correction.

> *The SIL rated systems and related circuits shall consist of: the driving-machine motor control system shall consist of a TKE, model HVI-22 ~~HW, High Voltage~~* ***or HVI-44*** *Inverter containing a Safe Torque Off printed circuit board assembly (STO). The STO shall be labeled or marked with a SIL rating (not less than SIL3), the name or mark of the certifying organization and SIL certification number FS/71/220, followed by the applicable revision number (as in FS/71/220/23/1060).*

2. The Applicant asserts that the revisions requested above allow for an alternative inverter device to accommodate lower electrical supply conditions provided by the power company.

3. Cal/OSHA recently reviewed the TK Elevator HVI 44 Inverter for compliance with A17.5 Elevator and Escalator Electrical Equipment certification standards and IEC 61508-2 and IEC 61508-3 SIL Rating Standards. On December 5, 2025, the Elevator

Unit issued an amended Acceptance Memorandum affirming compliance with the Elevator Safety Orders CCR Tile 8, Group IV, 3141.3 Static Controls.

4. Cal/OSHA believes that the Applicant's proposal to modify the existing condition provides equivalent safety.

D. Decision and Order

1. Permanent Variance Application No. 25-V-117M1 is conditionally GRANTED, thereby modifying Board records, such that, without change in variance location, each conveyance being the subject of Permanent Variance No. 25-V-117 and any previously granted modifications therewith, shall have the following edit to (E) Decision and Order, Subsection (3), Paragraph (3.1):

   The SIL rated systems and related circuits shall consist of: the driving-machine motor control system shall consist of a TKE, model HVI-22 ~~HW, High Voltage~~ ***or HVI-44*** *Inverter containing a Safe Torque Off printed circuit board assembly (STO). The STO shall be labeled or marked with a SIL rating (not less than SIL3), the name or mark of the certifying organization and SIL certification number FS/71/220, followed by the applicable revision number (as in FS/71/220/23/1060).*

2. Permanent Variance No. 25-V-117, being only modified as to include the optional HVI-44 inverter language above, is otherwise unchanged and remaining in full force and effect, as hereby incorporated by reference into Modification of Permanent Variance 25-V-117M1.

3. The applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way that the Applicant was required to notify them of the application for permanent variance, sections 411.2 and 411.3.

4. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed for its issuance.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

Kelly Chau, Hearing Officer

Dated: January 28, 2026

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: KONE Sleep Mode Escalator Alterations	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-339	CCMH San Diego LLC	333 W. Harbor Dr. San Diego, CA 92101	4

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Fuei Saetern with KONE, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21,2026 the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Based upon the record of this proceeding, the Board finds the following: Applicant proposes to perform alterations to 4 existing escalators that include a "sleep mode" capability that will cause the escalator to run at a reduced speed when not in use to conserve energy. This arrangement does not comply with the Elevator Safety Orders that prohibit the intentional variation of an escalator's speed after start-up, and thus variance is requested from California Code of Regulations, For this reason, the Applicant requires a permanent variance from the provisions of California Code of Regulations, Title 8, Elevator Safety Orders, Group IV, Section 3141.2 [ASME A17.1-2004 sections 8.7.6.1.1 (8.7.1.1) and 8.7.6.1.6] with the relevant code sections being ASME A17.1-2004, sections 6.1.4.1 and 6.1.6.4, regarding the variation of escalator speed and handrail speed monitoring.

2. Applicant submitted a declaration signed under penalty of perjury stating the existing escalators will be altered to add sleep mode functionality. It is understood by the Board and Cal/OSHA that Applicant wishes to request a variance from section 3141.2 [ASME A17.1-2004 sections 8.7.6.1.1 and 8.7.6.1.6].

3. ASME A17.1-2004, section 8.7.6.1.6 states:

    - 8.7.6.1.6 Handrails. Any alteration to the handrails or handrail system shall require conformance with 6.1.3.2.2, 6.1.3.4.1 through 6.1.3.4.4, 6.1.3.4.6, 6.1.6.3.12, and 6.1.6.4.

4. The Applicant's proposed "sleep mode" function is similar to other installations for which a permanent variance has been granted (Permanent Variance No. 14-V-129). In this previous variance decision it was concluded by the Board, that a variance also be granted from section 3141.11 [ASME A17.1-2004, section 6.1.6.4] regarding handrail speed monitoring. ASME A17.1-2004, section 6.1.4.1, states:

    - 6.1.4.1 Limits of Speed. The rated speed shall be not more than 0.5 m/s (100 ft/min), measured along the centerline of the steps in the direction of travel. The speed attained by an escalator after start-up shall not be intentionally varied.

    - The purpose of this regulation is to ensure that the speed of the escalator during normal operation is kept constant to prevent passengers from losing their balance.

5. The Applicant contends that equivalent safety is achieved through the use of a controller that is capable of varying the escalator drive motor speed in conjunction with dual redundant sensors strategically placed at each end of the unit to detect passenger traffic. When the sensors indicate a lack of traffic approaching the escalator, for a specified amount of time not less than three times the amount of time to transfer a passenger between landings, the control system will initiate the "sleep mode" function, decelerating the escalator to a "crawling speed", no less than 0.05 m/s (10 ft./min). If passenger traffic is detected while the escalator is in "Sleep Mode," a signal will be sent to the controller to "wake up" resulting in the escalator accelerating to normal operating speed within 1.5 seconds at a rate no greater than 1 ft/sec^2.

6. Per Applicant, the sensors used to detect passenger traffic would provide coverage able to detect passengers at a distance greater than a walking person could travel in 2 seconds, which

will ensure the escalator is running at normal speed prior to passenger boarding.

7. Applicant proposes that if passenger traffic is detected approaching the escalator opposite the motion of the escalator steps while in “sleep mode”, an alarm will sound and the escalator will exit “sleep mode” and accelerate until it reaches normal operating speed at a rate no greater than 1 ft/sec2. This arrangement is intended to discourage passengers from entering the escalator opposite the motion of the steps while at reduced speed.

8. As proposed, the sensors used to detect passenger traffic are to be installed and arranged in a double redundant, fail-safe fashion with two sensors installed at each end of the escalator providing the same coverage field. This arrangement is intended to allow for passenger traffic detection in the case of any single sensor failure and provide for signal comparison by the controller to detect sensor failure. In the event of a detected failure of any one of the passenger traffic sensors, “sleep mode” would be disabled and the escalator would remain at normal operating speed until all sensors have resumed normal function. In addition, the passenger traffic sensors are to be wired to the escalator controller in a fail-safe manner that prevents “sleep mode” activation if the wiring is cut or disconnected.

9. ASME A17.1-2004, section 8.7.6.1.1 states:

    - 8.7.6.1.1. General Requirements. Any alteration to an escalator shall comply with 6.1.6.1, 6.1.6.1.1, 6.1.6.2.1, 6.1.6.3.1, 6.1.6.3.5, 6.1.6.7, 8.7.1.1, and 8.7.1.2.

10. Cal/OSHA has applied ASME A17.1-2004 section 8.7.6.1.1 (reference to section 8.7.1.1) to the prohibition of intentionally varying the travel speed under section 6.1.4.1.

11. Cal/OHSA notes in its Review of Application (Exhibit PD-4) that the Applicant proposed “sleep mode” function meets the requirements of ASME A17.1-2010, section 6.1.4.1.2 regarding the varying the speed of an escalator after start-up. For this reason among others identified within the its Review of Application, Cal/OSHA advises that equivalent or superior safety will be provided by grant of permanent variance in this matter, as conditionally limited per the below Decision and Order.

12. ASME A17.1-2010, section 6.1.4.1.2, states:

    - Variation of the escalator speed after start-up shall be permitted provided the escalator installation conforms to all of the following:

        a. The acceleration and deceleration rates shall not exceed 0.3 m/s^2 (1.0 ft/sec^2).

        b. The rated speed is not exceeded.

        c. The minimum speed shall be not less than 0.05 m/s (10 ft/min).

        d. The speed shall not automatically vary during inspection operation.

        e. Passenger detection means shall be provided at both landings of the escalator such that

            1. detection of any approaching passenger shall cause the escalator to accelerate to or maintain the full escalator speed conforming to 6.1.4.1.2(a) through (d)

            2. detection of any approaching passenger shall occur sufficiently in advance of boarding to cause the escalator to attain full operating speed before a passenger walking at normal speed [1.35 m/s (270 ft/min)] reaches the

combplate

3. passenger detection means shall remain active at the egress landing to detect any passenger approaching against the direction of escalator travel and shall cause the escalator to accelerate to full rated speed and sound the alarm (see 6.1.6.3.1) at the approaching landing before the passenger reaches the combplate

f. Automatic deceleration shall not occur before a period of time has elapsed since the last passenger detection that is greater than 3 times the amount of time necessary to transfer a passenger between landings.

g. Means shall be provided to detect failure of the passenger detection means and shall cause the escalator to operate at full rated speed only."

13. Cal/OSHA states correctly in its Review of Application, that Applicant's proposed "sleep mode" function is materially similar to other installations for which a permanent variance has been granted (Permanent Variance No. 14-V-129). In these previous variance decisions it was concluded that a variance was required from ASME A17.1 2004, section 6.1.6.4 regarding handrail speed monitoring, and the concluding conditional grant of variance provided for the disabling of the handrail-speed monitoring device while the escalator is operating in slow speed "sleep mode."

14. ASME A17.1-2004, section 6.1.6.4, states:

- Handrail Speed Monitoring Device. A handrail speed monitoring device shall be provided that will cause the activation of the alarm required by 6.1.6.3.1(b) without any intentional delay, whenever the speed of either handrail deviates from the step speed by 15% or more. The device shall also cause electric power to be removed from the driving-machine motor and brake when the speed deviation of 15% or more is continuous within a 2 s to 6 s range. The device shall be of the manual-reset type.
- The intent of this regulation is to prevent the destabilization of passengers by maintaining the potential relationship of the moving elements with which passengers interaction while riding.

15. The Applicant intends to disable the handrail speed monitoring during sleep mode operation.

16. Cal/OSHA advises that the proposed "sleep mode" system incorporating the proposed hand rail speed control specifications, subject to all conditions and limitations of the below Decision and Order will provide for safety equivalence.

17. The proposed "sleep mode" system functions and devices are materially comparable to other installations for which permanent variance previously has been granted by the Board (e.g. Permanent Variance No. 13-V-153, 14-V-129, 15-V-236, 16-V-069), absent, to Cal/OSHA's reported knowledge, adverse effect upon passenger or workplace safety or health.

18. Cal/OSHA recommends that conditionally limited grant of permanent variance in this matter, per the below Decision and Order, will provide for passenger safety and occupational safety and health equivalent or superior to that would otherwise prevail per the subject Elevator Safety Order requirements.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

The application is conditionally GRANTED as specified below, and to the limited extent, as of the date the Board adopts this Proposed Decision, at the specified location, shall have permanent variance from Applicant requires a permanent variance from the provisions of section 3141.2 [ASME A17.1-2004 sections 8.7.6.1.1 (8.7.1.1) and 8.7.6.1.6] with the relevant code sections being ASME A17.1-2004, sections 6.1.4.1 and 6.1.6.4, regarding the variation of escalator speed and handrail speed monitoring, subject to each and all of the following requirements and limitations:

1. The Applicant may intentionally vary the escalator speed and install proximity sensors for traffic detection subject to the following:
    a. The rate of acceleration and deceleration shall not exceed 0.3 m/s^2 (1 ft/sec^2) when transitioning between speeds.
    b. Failure of a single proximity sensor including its associated circuitry, shall cause the escalator to revert to its normal operating speed at an acceleration of not more than 0.3 m/s2 (1 ft/sec^2).
    c. Automatic deceleration shall not occur before a period of time of not less than three times the time it takes a passenger to ride from one landing to the other at normal speed has elapsed.
    d. Detection of any passenger shall cause the escalator to reach full speed before a passenger, walking at 4.5ft/sec, reaches the comb plate.
    e. The passenger detection means shall detect a person within a sufficient distance along all possible paths to the escalator that do not require climbing over barriers or escalator handrails to assure that the escalator attains full operating speed before a person walking at 4.5 ft/sec reaches the escalator comb plate. The minimum detection distance shall be calculated according to the following formula or alternatively according to Appendix 1 (Detection Distance Sleep Mode Operation) attached hereto and incorporated herein by this reference:
        - **$d = (V_f - V_s) \times (V_w / a)$** where
            - d = detection distance (ft)
            - V_f = normal speed (ft/min) [not to exceed 100 ft/min]
            - V_s = slow "sleep" speed (ft/min) [not less than 10 ft/min]
            - V_w = passenger walking speed (4.5 ft/sec)

- a = acceleration/deceleration rate (ft/sec^2)[not to exceed 1 ft/sec^2]

f. Detection of any passenger approaching against the direction of escalator travel shall cause the escalator to reach full speed before a passenger, walking at 4.5 ft/sec, reaches the comb plate and shall cause the escalator alarm to sound. The sounding of the alarm may include a 3 to 5 second alarm or three 1 second alarm soundings.

g. The minimum speed of the escalator shall not be less than 0.05 m/s (10 ft/min). The "sleep mode" functionality shall not affect the escalator inspection operation. The speed of the escalator shall not vary during Inspection Mode.

h. There shall be two means of detecting passengers at each end of the escalator for redundancy and for detection of failure in the passenger detection means.

i. The passenger sensors (detectors) at each end of the escalator must be verified by the control system for proper operation in the following manner:

   1. If any of the passenger detection sensors remains tripped for at least 5 minutes but no more than 10 minutes, then the control system shall generate a fault to indicate which sensor is faulted while causing the escalator to exit the Sleep Mode and remain at the normal run speed until the faulted sensor begins to function properly.

   2. If one of the paired sensors at either end of the escalator does not trip while the other paired sensor trips at least five times but no more than ten times, the control system shall generate a fault to indicate which sensor is faulted while causing the escalator to exit the Sleep Mode and remain at the normal run speed until the faulted sensor begins to function properly.

j. The handrail speed monitoring device required by section 6.1.6.4 may be disabled while the escalator is operating in the slow speed (Sleep Mode) condition.

2. The Applicant shall have the controller schematic diagrams available in the control space together with a written explanation of the operation of the controller.

3. An annual test shall be conducted by a Certified Competent Conveyance Mechanic (CCCM) employed by a Certified Qualified Conveyance Company (CQCC) which maintains and services the escalators, to demonstrate that the escalator is transitioning between "Normal Mode" and "Sleep Mode" and back in conformance with the terms of this variance. The instrumentation used shall be capable of allowing the CCCM to determine the acceleration and deceleration rates of the escalator.

4. The results of each annual test required by Condition No. 3 shall be submitted to the appropriate Elevator Unit District Office in tabular and graphic form (speed vs. time).

5. Whenever practicable, as determined by the Applicant and subject to the concurrence of Cal/OSHA, the variable speed system is to be installed without the installation of new bollards or other such new structures, if the bollards or other structures would impede passenger movement at the destination end of the escalator. If new bollards or other such structures of that sort are constructed in connection with the variable speed system, the Applicant will take all practicable steps to minimize the impact of same on the movement of passengers at the destination end of the escalator.

6. Any Certified Qualified Conveyance Company (CQCC; elevator contractor) performing inspection, maintenance, servicing or testing of the escalators shall be provided a copy of the variance decision.
7. Cal/OSHA shall be notified when the escalator is ready for inspection, and the escalator shall be inspected by Cal/OSHA and a "Permit to Operate" issued before the escalator may be placed in service.
8. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
9. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in procedural accordance with section 411, et. seq.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 28, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-451	SSF Battery Point LP	3000 David St. Crescent City, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-452	Group One Integrity, Rosemont LLC	517 N. Rosemont Avenue Los Angeles, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 5, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-453	IDEC Corporation	2200 Faraday Avenue Carlsbad, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each

Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-454	ISF Ativo Santa Clarita LLC	16330 Village Way Santa Clarita, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each

Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-455	Lincoln Beach LP	208 S. Beach Blvd. Anaheim, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-456	Long Beach Community College District	LBCCD LAC- Building E, Liberal Arts Campus 4901 East Carson St. Long Beach, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-457	Montrose Street, LLC	1925 Montrose Street Los Angeles, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-458	Oakland Pacific Associates II, A California Limited Partnership	The Courtyards on International 10550 International Blvd. Oakland, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing

PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-459	Or Hachaim Academy	6017 Laurel Canyon Blvd. North Hollywood, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-460	Rose Hill Courts II Housing Partners, L.P.	Rose Hill Court Phase 2 - Building D 3510 N. Boundary Ave. Los Angeles, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-462	Compton College	CCCD Compton College- Student Housing 1111 E. Artesia Boulevard Compton, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table

PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the

subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance

record subject to ASME A17.1-2004, section 8.6.1.4).

f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

   a. The width and thickness in millimeters or inches;

   b. The manufacturer's rated breaking strength in (kN) or (lbf);

   c. The name of the person or organization that installed the flat coated steel belts;

   d. The month and year the flat coated steel belts were installed;

   e. The month and year the flat coated steel belts were first shortened;

   f. The name or trademark of the manufacturer of the flat coated steel belts; and

   g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

   a. The number of belts;

   b. The belt width and thickness in millimeters or inches; and

   c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

   a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

   b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

   c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

e. The applicant shall provide durable signs with lettering not less than ½ inch on a contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).

h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon request.

12. The speed governor rope and sheaves shall comply with the following:

    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.

    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.

    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:

    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.

    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.

15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.

16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.

17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.

18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives

are to be notified of docketed permanent variance applications.

19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-463	Daley Center Drive Associates LLC, A Delaware Limited Liability Company	9825 Stonecrest Blvd. San Diego, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-464	Nueva Day School	Nueva School Arts & Admin. Building 6565 Skyline Blvd. Hillsborough, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-465	The Grant at Mission Trails LP	5945 Mission Gorge Road San Diego, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-466	UC Madera Owner LLC	498 W. San Carlos Street San Jose, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Mitsubishi Elevators (Group IV)	Permanent Variance Nos.: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicant") below have applied for permanent variance from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-468	The Broad	221 S. Grand Ave. Los Angeles, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer, Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, Matt Jaskiewicz with Mitsubishi Electric, Elevator appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. At the hearing, documentary and oral evidence was received, and by stipulation of all parties, documents were accepted into evidence:

Exhibit Number	Description of Exhibit
PD-1	Permanent variance applications per section A.1 table
PD-2	OSHSB Notice of Hearing
PD-3	Cal/OSHA Review of variance application
PD-4	Review Draft-1 Proposed Decision

4. Official Notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed and the matter taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each section A table specified Applicant intends to utilize Mitsubishi elevators at the location and in the number stated in the table in Item A. The installation contracts for these elevators were signed on or after May 1, 2008, thus making the elevators subject to the Group IV Elevator Safety Orders.

2. The Board takes official notice and incorporates herein, Subsections D.3 through D.5 of the February 20, 2014, Decision of the Board in Permanent Variance File No. 13-V-270.

3. As reflected in the record of this matter, including Cal/OSHA evaluation as PD-3, and testimony at hearing, it is the professionally informed opinion of Cal/OSHA, that grant of requested variance, subject to conditions and limitations in substantial conforming with those set out per below Decision and Order, will provide Occupational Safety and Health equivalent or superior to that provided by the safety order requirements from which variance is sought.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicant's proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

a. The car top railing may be inset only to the extent necessary to clear obstructions when the conveyance is located at the top landing to perform work on the machine and/or governor.

b. Serviceable equipment shall be positioned so that mechanics, inspectors, and others working on the car top can remain positioned on the car top within the confines of the railings and do not have to climb on or over railings to perform adjustment, maintenance, minor repairs, inspections, or similar tasks. Persons performing those tasks are not to stand on or climb over railing, and those persons shall not remove handrails unless the equipment has been secured from movement and approved personal fall protection is used.

c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall, and shall be beveled from an intermediate or bottom rail to the outside of the car top.

d. The top surface of the beveled area shall be clearly marked. The markings shall consist of alternating 4-inch red and white diagonal stripes.

e. The Applicant shall provide a durable sign with lettering not less than ½-inch high on a contrasting background. The sign shall be located on the inset top railing; the sign shall be visible from the access side of the car top, and the sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING.
PERSONNEL ARE PROHIBITED FROM REMOVING HANDRAIL
UNLESS THE EQUIPMENT HAS BEEN SECURED FROM MOVEMENT
AND APPROVED PERSONAL FALL PROTECTION IS USED.

6. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing will be measured from the car top and not from the required bevel).

7. A mechanical means (e.g., locking bar mechanism) that will secure the car to the guide rail to prevent unintended movement shall be provided and used during machine and/or governor car-top work. The mechanical means (e.g., locking bar mechanism) shall have a safety factor of not less than 3.5 for the total unbalanced load.

8. An electrical switch or a lockout/tagout procedure shall be provided that will remove power from the driving machine and brake when the mechanical means (e.g., locking bar mechanism) is engaged.

9. In order to inhibit employees from working outside the car top railing, sections shall not be hinged and they shall be installed by means that will inhibit (but not necessarily completely preclude) removal. The Applicant shall ensure that all persons performing work that requires removal of any part of the car top railing are provided with fall protection that is appropriate and suitable for the assigned work. That fall protection shall consist of a personal fall arrest system or fall restraint system that complies with section 1670.

10. The bevel utilized by the Applicant in accordance with the variance granted from ASME A17.1-2004, section 2.10.2.4 shall slope at not less than 75 degrees from the horizontal to serve as the toe board; however, that slope may be reduced to a minimum of 40 degrees from the horizontal as may be required for sections where machine encroachment occurs.

11. If the Applicant directs or allows its employees to perform tasks on the car top, the Applicant shall develop, implement, and document a safety training program that shall provide training to Applicant employees. Components of the training shall include, but not necessarily be limited to, the following: car blocking procedures; how examination, inspection, adjustment, repair, removal and replacement of elevator components are to be performed safely, consistent with the requirements of the variance conditions; applicable provisions of the law and other sources of safety practices regarding the operation of the elevator. A copy of the training program shall be located in the control room of each elevator that is the subject of this variance, and a copy of the training program shall be attached to a copy of this variance that shall be retained in any building where an elevator subject to this variance is located. The Applicant shall not allow Certified Qualified Conveyance Company (CQCC) or other contractor personnel to work on the top of any elevator subject to this variance unless the Applicant first ascertains from the CQCC or other contractor that the personnel in question have received training equivalent to, or more extensive than, the training components referred to in this condition.

12. Any CQCC performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.

13. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.

14. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.

15. This Decision and Order shall remain in effect unless duly modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 27, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: KONE Monospace 500 Elevators (Group IV)	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-469	Victoria Gardens Investor, L.L.C.	12323 Cultural Center Drive Rancho Cucamonga, CA	5

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on via videoconference by the Board with Hearing Officer, Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Fuei Saetern, with KONE INC., appeared on behalf of each Applicant; and Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing

PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each respective Applicant intends to utilize the KONE, Inc. Monospace 500 type elevator, in the quantity, at the location, specified per the above section A.1 table.
2. The installation contract for this elevator was or will be signed on or after May 1, 2008, thus making the elevator subject to the Group IV Elevator Safety Orders.
3. Each Applicant proposes to use hoisting ropes that are 8 mm in diameter which also consist of 0.51 mm diameter outer wires, in variance from the express requirements of ASME A17.1-2004, section 2.20.4.
4. In relevant part, ASME A17.1-2004, section 2.20.4 states:

   2.20.4 Minimum Number and Diameter of Suspension Ropes

   …The minimum diameter of hoisting and counterweight ropes shall be 9.5 mm (0.375 in.). Outer wires of the ropes shall be not less than 0.56 mm (0.024 in.) in diameter.
5. An intent of ASME A17.1-2004, section 2.20.4, is to ensure that the number, diameter, and construction of suspension ropes are adequate to provided safely robust and durable suspension means over the course of the ropes' foreseen service life.
6. KONE has represented to Cal/OSHA, having established an engineering practice for purposes of Monospace 500 elevator design, of meeting or exceeding the minimum factor of safety of 12 for 8 mm suspension members, as required in ASME A17.1-2010 - under which, given that factor of safety, supplemental broken suspension member protection is not required.
7. Also, each Applicant proposes as a further means of maintaining safety equivalence, monitoring the rope in conformity with the criteria specified within the *Inspector's Guide to 6 mm Diameter Governor and 8 mm Diameter Suspension Ropes for KONE Elevators* (per Application attachment "B", or as thereafter revised by KONE subject Cal/OSHA approval).
8. In addition, each Applicant has proposed to utilize 6 mm diameter governor ropes in variance from Title 8, section 3141, incorporated ASME A17.1-2004, section 2.18.5.1.
9. ASME A17.1-2004, section 2.18.5.1, specifies, in relevant part:

   2.18.5.1 Material and Factor of Safety.

   … [Governor ropes] not less than 9.5 mm (0.375 in.) in diameter. The factor of safety of governor ropes shall be not less than 5…
10. The Board takes notice of section 3141.7, subpart (a)(10):

    A reduced diameter governor rope of equivalent construction and material to that required by

ASME A17.1-2004, is permissible if the factor of safety as related to the strength necessary to activate the safety is 5 or greater;

11. Applicants propose use of 6mm governor rope having a safety factor of 5 or greater, in conformity with section 3141.7(a)(10), the specific parameters of which, being expressly set out within the Elevator Safety Orders (ESO), take precedence over more generally referenced governor rope diameter requirements per ASME A17.1-2004, section 2.18.5.1. Accordingly, the governor rope specifications being presently proposed, inclusive of a factor of safety of 5 or greater, would comply with current requirements, and therefore not be subject to issuance of permanent variance.

12. Absent evident diminution in elevator safety, over the past decade the Board has issued numerous permanent variances for use in KONE (Ecospace) elevator systems of 8 mm diameter suspension rope materially similar to that presently proposed (e.g. Permanent Variance Nos. 06-V-203, 08-V-245, and 13-V-303).

13. As noted by the Board in permanent Variance Nos. 18-V-044, and 18-V-045, Decision and Order Findings, subpart B.17 (hereby incorporated by reference), the strength of wire rope operating as an elevator's suspension means does not remain constant over its years of projected service life. With increasing usage cycles, a reduction in the cross-sectional area of the wire rope normally occurs, resulting in decreased residual strength. This characteristic is of particular relevance to the present matter because, decreasing wire rope diameter is associated with a higher rate of residual strength loss. This foreseeable reduction in cross-sectional area primarily results from elongation under sheave rounding load, as well as from wear, and wire or strand breaks. However, these characteristics need not compromise elevator safety when properly accounted for in the engineering of elevator suspension means, and associated components.

14. The presently proposed wire rope is Wuxi Universal steel rope Co LTD. 8 mm 8x19S+8x7+PP, with a manufacturer rated breaking strength of 35.8 kN, and an outer wire diameter of less than 0.56 mm, but not less than 0.51 mm. Cal/OSHA's safety engineer has scrutinized the material and structural specifications, and performance testing data, of this particular proposed rope, and concluded it will provide for safety equivalent to ESO compliant 9.5 mm wire rope, with 0.56 mm outer wire (under conditions of use included within the below Decision and Order).

15. The applicant supplies tabulated data regarding the "Maximum Static Load on All Suspension Ropes." To obtain the tabulated data, the applicant uses the following formula derived from ASME A17.1 2004, section 2.20.3:

$$W = \frac{(S \times N)}{f}$$ *where:*

W = maximum static load imposed on all car ropes with the car and its rated load at any position in the hoistway

N = number of runs of rope under load. For 2:1 roping, N shall be two times the number of ropes used, etc.

S = manufacturer's rated breaking strength of one rope

f = the factor of safety from Table 2.20.3

16. ASME A17.1-2010 sections 2.20.3 and 2.20.4 utilize the same formula, but provide for use of suspension ropes having a diameter smaller than 9.5 mm, under specified conditions, key

among them being that use of ropes having a diameter of between 8 mm to 9.5 mm be engineered with a factor of safety of 12 or higher This is a higher minimum factor of safety than that proposed by Applicant but a minimum recommended by Cal/OSHA as a condition of variance necessary to the achieving of safety equivalence to 9.5 mm rope

17. Cal/OSHA is in accord with Applicant, in proposing as a condition of safety equivalence, that periodic physical examination of the wire ropes be performed to confirm the ropes continue to meet the criteria set out in the (Application attachment) *Inspector's Guide to 6 mm Diameter Governor and 8 mm Diameter Suspension Ropes for KONE Elevators*. Adherence to this condition will provide an additional assurance of safety equivalence, regarding smaller minimum diameter suspension rope outer wire performance over the course of its service life.
18. Cal/OSHA, by way of written submission to the record (Exhibit PD3), and stated position at hearing, is of the well informed opinion that grant of permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each Application being the subject of this proceeding, per above section A.1 table, is conditionally GRANTED, to the extent that each such Applicant shall be issued permanent variance from section 3141 incorporated ASME A17.1-2004, section 2.20.4, in as much as it precludes use of suspension rope of between 8 mm and 9.5 mm, or outer wire of between 0.51 mm and 0.56 mm in diameter, at such locations and numbers of Group IV KONE Monospace 500 elevators identified in each respective Application, subject to the following conditions:

1. The diameter of the hoisting steel ropes shall be not less than 8 mm (0.315 in) diameter and the roping ratio shall be two to one (2:1).
2. The outer wires of the suspension ropes shall be not less than 0.51 mm (0.02 in.) in diameter.
3. The number of suspension ropes shall be not fewer than those specified per hereby incorporated Decision and Order Appendix 1 Table.
4. The ropes shall be inspected annually for wire damage (rouge, valley break etc.) in accordance with "KONE, Inc. Inspector's Guide to 6 mm diameter and 8 mm diameter steel ropes for KONE Elevators" (per Application Exhibit B, or as thereafter amended by KONE subject to Cal/OSHA approval).
5. A rope inspection log shall be maintained and available in the elevator controller room / space at all times.
6. The elevator rated speed shall not exceed those speeds specified per the Decision and Order Appendix 1 Table.

7. The maximum suspended load shall not exceed those weights (plus 5%) specified per the Decision and Order Appendix 1 Table.
8. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of the elevator equipment in the hoistway is required. If the service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.
9. The installation shall meet the suspension wire rope factor of safety requirements of ASME A17.1-2013 section 2.20.3.
10. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing or testing the elevators shall be provided a copy of this variance decision.
11. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA and a "Permit to Operate" issued before the elevator is placed in service.
12. The Applicant shall comply with suspension means replacement reporting condition per hereby incorporated Decision and Order Appendix 2.
13. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
14. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the procedural manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 28, 2026

Kelly Chau, Hearing Officer

APPENDIX 1

Variance Number	Elevator ID	Minimum Quantity of Ropes (per Condition 3)	Maximum Speed in Feet per Minute (per Condition 6)	Maximum Suspended Load (per Condition 7)
25-V-469	1	8	200	13,207
25-V-469	2	8	200	13,207
25-V-469	3	8	200	13,207
25-V-469	4	8	200	13,207
25-V-469	5	8	200	13,207

APPENDIX 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-471	11250 La Grange LLC	11250 W. La Grange Los Angeles, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-474	HIW Associates, LP	2040 Harbor Island Dr. San Diego, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates and Wolter Geesink with Otis Elevator Company appeared on behalf of each Applicant; and Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

Kelly Chau, Hearing Officer

DATED: February 2, 2026

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-475	Liberty Homes, LLC	39470 Murrieta Hot Springs Rd. Murrieta, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as

specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-476	Pacific Square San Gabriel, LLC	700 S. San Gabriel Blvd. San Gabriel, CA	5

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-477	Pacific Square San Gabriel, LLC	Pacific Square San Gabriel MU 700 S. San Gabriel Blvd. San Gabriel, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing

PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-478	Regional Street Investors, L.P.	6543 Regional Street Dublin, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-479	Santa Barbara Neighborhood Clinics	621 W. Micheltorena St. Santa Barbara, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2O and/or Gen3 Peak with Variant Governor Rope and Sheaves & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-480	State of California	New Capital Annex Building 1315 10th St. Sacramento, CA	18

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Applicable Regulation

1. The Applicants request variance from some or all of the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:
    a. Suspension Means: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4, and 2.20.9.5.4 (to permit the use of the Elastomeric Coated Steel Belts proposed by the Applicant in lieu of circular steel suspension ropes.);
    b. Cartop Railing: 2.14.1.7.1 (to permit the use of the car top railing system proposed by the Applicant, where the railing system is located inset from the elevator car top perimeter);
    c. Inspection transfer switch: 2.26.1.4.4(a) (to permit the inspection transfer switch to reside at a location other than the machine room);
    d. Seismic reset switch: 8.4.10.1.1(a)(2)(b) (to permit the seismic reset switch to reside at a location other than the machine room);
    e. Governor Rope Diameter: 2.18.5.1 (to permit the use of the governor rope proposed by the Applicant, where the rope has a diameter of 8 mm [0.315 in.]); Note: A variance from the section above is not required. However, the Board has included a variance from this code requirement in similar previous variances.
    f. Pitch Diameter: 2.18.7.4 (to permit the use of the speed governor system, proposed by the Applicant, where the rope sheave pitch diameter is less than what is required by the Elevator Safety Orders).
    g. Minimum Inside Car Platform Dimensions: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

D. Findings of Fact

1. The Board incorporates by reference the findings stated in:
    a. Items 3 through 5.c, 5.e, and 5.f of the "Findings of Fact" section of the Proposed Decision adopted by the Board on February 19, 2009, in Permanent Variance No. 08-V-247;
    b. Item D.3 of the Proposed Decision adopted by the Board on July 16, 2009, in Permanent Variance No. 09-V-042;
    c. Item D.4 of the Proposed Decision adopted by the Board on September 16, 2010, in Permanent Variance No. 10-V-029;
    d. Items D.4, D.5, and D.7 of the Proposed Decision adopted by the Board on July 18, 2013, in Permanent Variance No. 12-V-146; and

e. Items D.4 and D.5 of the Proposed Decision adopted by the Board on September 25, 2014, in Permanent Variance No. 14-V-170.

f. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for OSHSB File No. 22-V-302 regarding medical emergency car dimensions.

2. Regarding requested variance in governor sheave diameter, and governor rope diameter, in variance from section 3141, incorporated ASME A17.1-2004, sections 2.18.7.4 and 2.18.5.1, respectively, the Board incorporates by reference the following previous findings of record: Items 8 through 12 of the Proposed Decision adopted by the Board on December 13, 2018, in Permanent Variance No. 18-V-425, and further substantiating bases per therein cited Permanent Variance Decisions of the Board.

3. The installation contracts for elevators, the subject of the permanent variance application, were signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders ("ESO").

4. Cal/OSHA safety engineers, by way of written submissions to the record (Exhibit PD-3), and positions stated at hearing, are of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

E. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

F. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, Applicant shall have permanent variances from section 3141 and from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- Suspension Means: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4, and 2.20.9.5.4 (To permit the use of the Elastomeric Coated Steel Belts proposed by the Applicant in lieu of circular steel suspension ropes.);
- Cartop Railing: 2.14.1.7.1 (To permit the use of the car top railing system proposed by the Applicant, where the railing system is located inset from the elevator car top perimeter);
- Inspection transfer switch: 2.26.1.4.4(a) (To permit the inspection transfer switch to reside at a location other than the machine room);
- Seismic reset switch: 8.4.10.1.1(a)(2)(b) (To permit the seismic reset switch to reside at a location other than the machine room);
- Governor Rope Diameter: 2.18.5.1 (To permit the use of the governor rope proposed by the

Applicant, where the rope has a diameter of 8 mm [0.315 in.]); Note: A variance from the section above is not required. However, the Board has included a variance from this code requirement in similar previous variances.

- Pitch Diameter: 2.18.7.4 (To permit the use of the speed governor system, proposed by the Applicant, where the rope sheave pitch diameter is less than what is required by the Elevator Safety Orders).
- Minimum Inside Car Platform Dimensions: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

The variance shall be subject to, and limited by, the following additional conditions:

1. Each elevator subject to this variance shall comply with all applicable Group IV Elevator Safety Orders and with all ASME provisions made applicable by those Group IV Elevator Safety Orders, except those from which variances are granted, as set forth in the prefatory portion of this Decision and Order.
2. The suspension system shall comply with the following:
    a. The coated steel belt shall have a factor of safety at least equal to the factor of safety that ASME A17.1-2004, section 2.20.3, would require for wire ropes if the elevator were suspended by wire ropes rather than the coated steel belt.
    b. Steel-coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.
    g. The installation of belts and connections shall be in conformance with the manufacturer's specifications, which shall be provided to Cal/OSHA.
3. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, a copy of which is attached hereto as Addendum 1 and incorporated herein by this reference.
4. The Applicant shall not utilize each elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device, and criteria for belt replacement, and shall make those procedures and criteria available to Cal/OSHA upon request.

5. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:
    a. The width and thickness in millimeters or inches;
    b. The manufacturer's rated breaking strength in (kN) or (lbf);
    c. The name of the person who, or organization that, installed the flat coated steel belts;
    d. The month and year the flat coated steel belts were installed;
    e. The month and year the flat coated steel belts were first shortened;
    f. The name or trademark of the manufacturer of the flat coated steel belts;
    g. Lubrication information.

6. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:
    a. The number of belts,
    b. The belt width and thickness in millimeters or inches, and
    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

7. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
8. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a), does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. When the inspection and test control panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
10. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.
11. If there is an inset car top railing:
    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs, or inspections. The Applicant shall not permit anyone to stand on or climb over the car top railing.
    b. The distance that the car top railing may be inset from the car top perimeter shall be limited to no more than 6 inches.
    c. All exposed areas of the car top outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

d. The top of the beveled area and/or the car top outside the railing, shall be clearly marked. The markings shall consist of alternating four-inch diagonal red and white stripes.

e. The Applicant shall provide, on each inset railing, durable signs with lettering not less than ½ inch on a contrasting background. Each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top, and not from the required bevel).

12. The speed governor rope and sheaves shall comply with the following:

    a. The governor shall be used in conjunction with a 8 mm (0.315 in.) diameter steel governor rope with 8-strand, regular lay construction.

    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.

    c. The governor sheaves shall have a pitch diameter of not less than 240 mm (9.45 in.).

13. Each elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen2(O) and/or Gen3 Peak elevator system the Applicant proposes to use, in accordance with the written procedures and criteria required by Condition No. 4 and the terms of this permanent variance.

14. All medical emergency service elevators shall comply with the following:

    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21- inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5 inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.

    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.

16. Cal/OSHA shall be notified when each elevator is ready for inspection. Each elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before each elevator is placed in service.

17. The Applicant shall be subject to the suspension means replacement reporting condition stated in Addendum 2; that condition is incorporated herein by this reference.

18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way that the Applicant was required to notify them of the application for permanent variance, per sections 411.2 and 411.3.

19. This Decision and Order shall remain in effect unless duly modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the procedural manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-481	The Trails at CMR CIC, LP	10200 Rancho Carmel Dr., Bldg. A San Diego, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-482	The Trails at CMR CIC, LP	Building B 10200 Rancho Carmel Dr. San Diego, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2O and/or Gen3 Peak with Variant Governor Rope and Sheaves (Group IV)	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-483	University of California Santa Barbara	UCSB San Benito Student Housing 584 Mesa Rd. Santa Barbara, CA	10

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Applicable Regulations

1. The Applicants request variance from some or all of the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

    a. Suspension Means: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4, and 2.20.9.5.4 (to permit the use of the Elastomeric Coated Steel Belts proposed by the Applicant in lieu of circular steel suspension ropes.);

    b. Cartop Railing: 2.14.1.7.1 to permit the use of the car top railing system proposed by the Applicant, where the railing system is located inset from the elevator car top perimeter);

    c. Inspection transfer switch: 2.26.1.4.4(a) (to permit the inspection transfer switch to reside at a location other than the machine room);

    d. Seismic reset switch: 8.4.10.1.1(a)(2)(b) (to permit the seismic reset switch to reside at a location other than the machine room);

    e. Governor Rope Diameter: 2.18.5.1 (to permit the use of the governor rope proposed by the Applicant, where the rope has a diameter of 8 mm [0.315 in.]); Note: A variance from the section above is not required. However, the Board has included a variance from this code requirement in similar previous variances.

    f. Pitch Diameter: 2.18.7.4 (to permit the use of the speed governor system, proposed by the Applicant, where the rope sheave pitch diameter is less than what is required by the Elevator Safety Orders).

D. Findings of Fact

1. The Board incorporates by reference the findings stated in:

    a. Items 3 through 5.c, 5.e, and 5.f of the "Findings of Fact" section of the Proposed Decision adopted by the Board on February 19, 2009, in Permanent Variance No. 08-V-247;

    b. Item D.3 of the Proposed Decision adopted by the Board on July 16, 2009, in Permanent Variance No. 09-V-042;

    c. Item D.4 of the Proposed Decision adopted by the Board on September 16, 2010, in Permanent Variance No. 10-V-029;

    d. Items D.4, D.5, and D.7 of the Proposed Decision adopted by the Board on July 18, 2013, in Permanent Variance No. 12-V-146; and

    e. Items D.4 and D.5 of the Proposed Decision adopted by the Board on September 25, 2014, in Permanent Variance No. 14-V-170.

2. Regarding requested variance in governor sheave diameter, and governor rope diameter, in variance from section 3141, incorporated ASME A17.1-2004, sections 2.18.7.4 and 2.18.5.1, respectively, the Board incorporates by reference the following previous findings of record: Items 8 through 12 of the Proposed Decision adopted by the Board on December 13, 2018, in Permanent Variance No. 18-V-425, and further substantiating bases per therein cited Permanent Variance Decisions of the Board.
3. The installation contracts for elevators, the subject of the permanent variance application, were signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders ("ESO").
4. Cal/OSHA's safety engineers, by way of written submission to the record (Exhibit PD-3), and positions stated at hearing, are of the well-informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order, will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

E. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

F. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, Applicant shall have permanent variances from section 3141 and from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- Suspension Means: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4, and 2.20.9.5.4 (To permit the use of the Elastomeric Coated Steel Belts proposed by the Applicant in lieu of circular steel suspension ropes.);
- Cartop Railing: 2.14.1.7.1 (To permit the use of the car top railing system proposed by the Applicant, where the railing system is located inset from the elevator car top perimeter);
- Inspection transfer switch: 2.26.1.4.4(a) (To permit the inspection transfer switch to reside at a location other than the machine room);
- Seismic reset switch: 8.4.10.1.1(a)(2)(b) (To permit the seismic reset switch to reside at a location other than the machine room);
- Governor Rope Diameter: 2.18.5.1 (To permit the use of the governor rope proposed by the Applicant, where the rope has a diameter of 8 mm [0.315 in.]); Note: A variance from the section above is not required. However, the Board has included a variance from this code requirement in similar previous variances.
- Pitch Diameter: 2.18.7.4 (To permit the use of the speed governor system, proposed by the Applicant, where the rope sheave pitch diameter is less than what is required by the Elevator

Safety Orders).

The variance shall be subject to, and limited by, the following additional conditions:

1. Each elevator subject to this variance shall comply with all applicable Group IV Elevator Safety Orders and with all ASME provisions made applicable by those Group IV Elevator Safety Orders, except those from which variances are granted, as set forth in the prefatory portion of this Decision and Order.
2. The suspension system shall comply with the following:
    a. The coated steel belt shall have a factor of safety at least equal to the factor of safety that ASME A17.1-2004, section 2.20.3, would require for wire ropes if the elevator were suspended by wire ropes rather than the coated steel belt.
    b. Steel-coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.
    g. The installation of belts and connections shall be in conformance with the manufacturer's specifications, which shall be provided to Cal/OSHA.
3. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, a copy of which is attached hereto as Addendum 1 and incorporated herein by this reference.
4. The Applicant shall not utilize each elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device, and criteria for belt replacement, and shall make those procedures and criteria available to Cal/OSHA upon request.
5. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:
    a. The width and thickness in millimeters or inches;
    b. The manufacturer's rated breaking strength in (kN) or (lbf);
    c. The name of the person who, or organization that, installed the flat coated steel belts;

d. The month and year the flat coated steel belts were installed;

e. The month and year the flat coated steel belts were first shortened;

f. The name or trademark of the manufacturer of the flat coated steel belts;

g. Lubrication information.

6. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

   a. The number of belts,

   b. The belt width and thickness in millimeters or inches, and

   c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

7. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.

8. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a), does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.

9. When the inspection and test control panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.

10. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

11. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs, or inspections. The Applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset from the car top perimeter shall be limited to no more than 6 inches.

    c. All exposed areas of the car top outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or the car top outside the railing, shall be clearly marked. The markings shall consist of alternating four-inch diagonal red and white stripes.

    e. The Applicant shall provide, on each inset railing, durable signs with lettering not less than ½ inch on a contrasting background. Each sign shall state:

CAUTION

DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top, and not from the required bevel).

12. The speed governor rope and sheaves shall comply with the following:

    a. The governor shall be used in conjunction with a 8 mm (0.315 in.) diameter steel governor rope with 8-strand, regular lay construction.

    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.

    c. The governor sheaves shall have a pitch diameter of not less than 240 mm (9.45 in.).

13. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.

14. Cal/OSHA shall be notified when each elevator is ready for inspection. Each elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before each elevator is placed in service.

15. The Applicant shall be subject to the suspension means replacement reporting condition stated in Addendum 2; that condition is incorporated herein by this reference.

16. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way that the Applicant was required to notify them of the application for permanent variance, per sections 411.2 and 411.3.

17. This Decision and Order shall remain in effect unless duly modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the procedural manner prescribed by the Board's regulations.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-484	University of California Santa Barbara	UCSB San Benito Student Housing 584 Mesa Rd. Santa Barbara, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 5, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-485	University of California Santa Barbara	UCSB San Benito Student Housing 584 Mesa Rd. Santa Barbara, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

   (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:

   ...

   (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

   The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

   This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
   The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-486	USS Trafalgar LLC	2903 4th Ave. San Diego, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each

Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-487	DBC III SPE LLC	Building 1 Parking Garage 1100 Inspiration Irvine, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Schindler 3300 with SIL-Rated Drive to De-energize Drive Motor (Group IV)	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicant") below have applied for permanent variance from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations[1], as follows:

Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-488	Phoenix 810 Pine LP	811 Pine Street Oakland, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational and Safety Health Standard Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer, Kelly Chau, both presiding and hearing the matter on its merit in accordance with section 426.

2 At the hearing, Pete Cuellar with Schindler Elevator Corporation appeared on behalf of each Applicant. Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

[1] Unless otherwise noted, references are to the California Code of Regulations, title 8.

Exhibit Number	Description of Exhibit
PD-1	Permanent variance applications per section A.1 table
PD-2	OSHSB Notice of Hearing
PD-3	Cal/OSHA Review of variance application
PD-4	Review Draft-1 of Proposed Decision

4. Official notice taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026 the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

Relevant Safety Order Provisions

Applicant seeks a permanent variance from section 3141 [ASME A17.1-2004, sections 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.5.4, 2.26.1.4.4(a), 8.4.10.1.1(a)(2)(B), 2.14.1.7.1, and 2.26.9.6.1]. The relevant language of those sections are below.

Suspension Means

Section 3141 [ASME A17.1-2004, section 2.20.1, Suspension Means] states in part:

> Elevator cars shall be suspended by steel wire ropes attached to the car frame or passing around sheaves attached to the car frame specified in 2.15.1. Ropes that have previously been installed and used on another installation shall not be reused. Only iron (low-carbon steel) or steel wire ropes, having the commercial classification "Elevator Wire Rope," or wire rope specifically constructed for elevator use, shall be used for the suspension of elevator cars and for the suspension of counterweights. The wire material for ropes shall be manufactured by the open-hearth or electric furnace process, or their equivalent.

Section 3141 [ASME A17.1-2004, section 2.20.2.1(b), On Crosshead Data Plate] states in part:

> The crosshead data plate required by 2.16.3 shall bear the following wire-rope data:
>
> (b) the diameter in millimeters (mm) or inches (in.)

Section 3141 [ASME A17.1-2004, section 2.20.2.2(a) and (f) On Rope Data Tag] states in part:

> A metal data tag shall be securely attached-to-one of the wire-rope fastenings. This data tag shall bear the following wire-rope data:

(a) the diameter in millimeters (mm) or inches (in.)

[…]

(f) whether the ropes were non preformed or preformed

Section 3141 [ASME A17.1-2004, section 2.20.3, Factor of Safety] states:

The factor of safety of the suspension wire ropes shall be not less than shown in Table 2.20.3. Figure 8.2.7 gives the minimum factor of safety for intermediate rope speeds. The factor of safety shall be based on the actual rope speed corresponding to the rated speed of the car.

The factor of safety shall be calculated by the following formula:

$$f = \frac{S\ x\ N}{W}$$

where:

N= number of runs of rope under load. For 2:1 roping, N shall be two times the number of ropes used, etc.

S= manufacturer's rated breaking strength of one rope

W= maximum static load imposed on all car ropes with the car and its rated load at any position in the hoistway

Section 3141 [ASME A17.1-2004, section 2.20.4, Minimum Number and Diameter of Suspension Ropes] states:

The minimum number of hoisting ropes used shall be three for traction elevators and two for drum-type elevators.

Where a car counterweight is used, the number of counterweight ropes used shall be not less than two.

The term "diameter," where used in reference to ropes, shall refer to the nominal diameter as given by the rope manufacturer.

The minimum diameter of hoisting and counterweight ropes shall be 9.5 mm (0.375 in.). Outer wires of the ropes shall be not less than 0.56 mm (0.024 in.) in diameter.

Section 3141 [ASME A17.1-2004, section 2.20.9.3.4] states:

Cast or forged steel rope sockets, shackle rods, and their connections shall be made of unwelded steel, having an elongation of not less than 20% in a gauge length of 50 mm (2 in.), when measured in accordance with ASTM E 8, and conforming to ASTM A 668, Class B for forged steel, and ASTM A 27, Grade 60/30 for cast steel, and shall be stress relieved. Steels of greater strength shall be permitted, provided they have an elongation of not less than 20% in a length of 50 mm (2 in.).

Section 3141 [ASME A17.1-2004, section 2.20.9.5.4] states:

When the rope has been seated in the wedge socket by the load on the rope, the wedge shall be visible, and at least two wire-rope retaining clips shall be provided to attach the termination side to the load-carrying side of the rope (see Fig. 2.20.9.5). The first clip shall be placed a maximum of 4 times the rope diameter above the socket, and the second clip shall be located within 8 times the rope diameter above the first clip. The purpose of the two clips is to retain the wedge and prevent the rope from slipping in the socket should the load on the rope be removed for any reason. The clips shall be designed and installed so that they do not distort or damage the rope in any manner.

Inspection Transfer Switch

Section 3141[ASME A17.1-2004, section 2.26.1.4.4(a), Machine Room Inspection Operation] states:

When machine room inspection operation is provided, it shall conform to 2.26.1.4.1, and the transfer switch shall be

(a) located in the machine room[.]

Seismic Reset Switch

Section 3141[ASME A17.1-2004, section 8.4.10.1.1(a)(2)(b), Earthquake Equipment] states:

(a) All traction elevators operating at a rated speed of 0.75 m/s (150 ft/min) or more and having counterweights located in the same hoistway shall be provided with the following:

(1) seismic zone 3 or greater: a minimum of one seismic switch per building

(2) seismic zone 2 or greater:

(a) a displacement switch for each elevator

(b) an identified momentary reset button or switch for each elevator, located in the control panel in the elevator machine room

Car-top Railings

Section 3141[ASME A17.1-2004, section 2.14.1.7.1] states:

A standard railing conforming to 2.10.2 shall be provided on the outside perimeter of the car top on all sides where the perpendicular distance between the edges of the car top and the adjacent hoistway enclosure exceeds 300 mm (12 in.) horizontal clearance.

SIL-Rated System to Inhibit Current Flow to AC Drive Motor

Section 3141[ASME A17.1-2004, section 2.26.9.6.1] states:

Two separate means shall be provided to independently inhibit the flow of alternating current through the solid state devices that connect the direct current power source to the alternating-current driving motor. At least one of the means shall be an electromechanical relay.

C. Findings of Fact

1. Each Applicant intends to utilize Schindler model 3300 MRL elevator cars, in the quantity, at the locations, specified per the above Section A.1 table.

2. The installation contract for these elevator was or will be signed on or after May 1, 2008, thus making the elevator subject to the Group IV Elevator Safety Orders.

3. The Schindler model 3300 MRL elevator cars are not supported by circular steel wire ropes, as required by the Elevator Safety Orders (ESO). They utilize non-circular elastomeric-coated steel belts and specialized suspension means fastenings.

4. No machine room is provided, preventing the inspection transfer switch from being located in the elevator machine room. The lack of machine room also prevents the seismic reset switch from being located in the elevator machine room.

5. Applicant proposes to relocate the inspection transfer switch and seismic reset switch in an alternative enclosure.

6. The driving machine and governor are positioned in the hoistway and restrict the required overhead clearance to the elevator car top.

7. Applicant proposes to insert the car-top railings at the perimeter of the car top.

8. Applicant intends to use an elevator control system, model CO NX100NA, with a standalone, solid-state motor control drive system that includes devices and circuits having a Safety Integrity Level (SIL) rating to execute specific elevator safety functions.

D. Conclusive Findings

A preponderence of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide

equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application being the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject to the following conditions:

Elevator Safety Orders:

• Suspension Means: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4, and 2.20.9.5.4 (Only to the extent necessary to permit the use of the Elastomeric-coated Steel Belts proposed by the Applicant, in lieu of circular steel suspension ropes.);

• Inspection transfer switch: 2.26.1.4.4(a) (Only to the extent necessary to permit the inspection transfer switch to reside at a location other than the machine room);

• Seismic reset switch: 8.4.10.1.1(a)(2)(b) (Only to the extent necessary to permit the seismic reset switch to reside at a location other than the machine room. room);

• Car-Top Railing: 2.14.1.7.1 (Only to the extent necessary to permit the use of the car-top railing system proposed by the Applicant, where the railing system is located inset from the elevator car top perimeter);

• Means of Removing Power: 2.26.9.6.1 (Only to the extent necessary to permit the use of SIL-rated devices and circuits as a means to remove power from the AC driving motor, where the redundant monitoring of electrical protective devices is required by the Elevator Safety Orders).

Conditions:

1. The elevator suspension system shall comply to the following:

    a. The suspension traction media (STM) members and their associated fastenings shall conform to the applicable requirements of ASME A17.1-2013, sections:

        2.20.4.3 – Minimum Number of Suspension Members
        2.20.3 – Factor of Safety
        2.20.9 – Suspension Member Fastening

    b. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection and testing of the STM members and fastenings and related monitoring and detection systems and criteria for STM replacement, and the Applicant shall make those procedures and criteria

available to the Certified Competent Conveyance Mechanic (CCCM) at the location of the elevator, and to Cal/OSHA upon request.

STM member mandatory replacement criteria shall include:

i. Any exposed wire, strand or cord;
ii. Any wire, strand or cord breaks through the elastomeric coating;
iii. Any evidence of rouging (steel tension element corrosion) on any part of the elastomeric-coated steel suspension member;
iv. Any deformation in the elastomeric suspension member such as, but not limited to, kinks or bends;

c. Traction drive sheaves must have a minimum diameter of 72 mm. The maximum speed of STM members running on 72 mm, 87 mm and 125 mm drive sheaves shall be no greater than 2.5 m/s, 6.0 m/s and 8.0 m/s respectively.

d. If any one STM member needs replacement, the complete set of suspension members on the elevator shall be replaced. Exception: if a new suspension member is damaged during installation, and prior to any contemporaneously installed STM having been placed into service, it is permissible to replace the individual damaged suspension member. STM members that have been installed on another installation shall not be re-used.

e. A traction loss detection means shall be provided that conforms to the requirements of ASME A17.1-2013, section 2.20.8.1. The means shall be tested for correct function annually in accordance with ASME A17.1-2013, section 8.6.4.19.12.

f. A broken suspension member detection means shall be provided that conforms to the requirements of ASME A17.1-2013, section 2.20.8.2. The means shall be tested for correct function annually in accordance with ASME A17.1-2013, section 8.6.4.19.13(a).

g. An elevator controller integrated bend cycle monitoring system shall monitor actual STM bend cycles, by means of continuously counting, and storing in nonvolatile memory, the number of trips that the STM makes traveling, and thereby being bent, over the elevator sheaves. The bend cycle limit monitoring means shall automatically stop the car normally at the next available landing before the bend cycle correlated residual strength of any single STM member drops below 80 percent of full rated strength. The monitoring means shall prevent the car from restarting. The bend cycle monitoring system shall be tested annually in accordance with the procedures required by condition 1b above.

h. The elevator shall be provided with a device to monitor the remaining residual strength of each STM member. The device shall conform to the requirements of Cal/OSHA Circular Letter E-10-04, a copy of which is attached hereto as Exhibit 1 and incorporated herein by reference.

i. The elevator crosshead data plate shall comply with the requirements of ASME A17.1-2013, section 2.20.2.1.

j. A suspension means data tag shall be provided that complies with the requirements of ASME A17.1-2013, section 2.20.2.2.

k. Comprehensive visual inspections of the entire length of each and all installed suspension members, to the criteria developed in condition 1b, shall be conducted and documented every six months by a CCCM.

l. The Applicant shall be subject to the requirements set out in Exhibit 2 of this Decision and Order, "Suspension Means Replacement Reporting Condition," Incorporated herein by this reference.

m. Records of all tests and inspections shall be maintenance records subject to ASME A17.1-2004, sections 8.6.1.2 and 8.6.1.4, respectively.

2. If the inspection transfer switch required by ASME A17.1-2004, section 2.26.1.4.4 does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the control/machinery room/space containing the elevator's control equipment in an enclosure secured by a lock openable by a Group 1 security key. The enclosure is to remain locked at all times when not in use.

3. If the seismic reset switch does not reside in the machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the control/machinery room/space containing the elevator's control equipment in an enclosure secured by a lock openable by a Group 1 security key. The enclosure is to remain locked at all times when not in use.

4. If there is an inset car-top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on the railings to perform adjustments, maintenance, repairs or inspections. The Applicant shall not permit anyone to stand or climb over the car-top railing.

    b. The distance that the railing can be inset shall be limited to not more than 6 inches.

    c. All exposed areas of the car top outside the car-top railing where the distance from the railing to the edge of the car top exceeds 2 inches, shall be beveled with metal, at an angle of not less than 75 degrees with the horizontal, from the mid or top rail to the outside of the car top, such that no person or object can stand, sit, kneel, rest, or be placed in the exposed areas.

    d. The top of the beveled area and/or car top outside the railing shall be clearly marked. The markings shall consist of alternating 4-inch diagonal red and white stripes.

e. The applicant shall provide durable signs with lettering not less than 1/2 inch on a contrasting background on each inset railing. Each sign shall state:

CAUTION
STAY INSIDE RAILING
NO LEANING BEYOND RAILING
NO STEPPING ON, OR BEYOND, RAILING

f. The Group IV requirements for car-top clearances shall be maintained (car-top clearances outside the railing will be measured from the car top and not from the required bevel).

5. The SIL-rated devices and circuits used to inhibit electrical current flow in accordance with ASME A17.1-2004, section 2.26.9.6.1 shall comply with the following:

a. The SIL-rated devices and circuits shall consist of a Variodyn SIL-3 rated Regenerative, Variable Voltage Variable Frequency (VVVF) motor drive unit, model VAF013 or VAF023, labeled or marked with the SIL rating (not less than SIL 3), the name or mark of the certifying organization, and the SIL certification number (968/FSP 1556.00), and followed by the applicable revision number (as in 968/FSP 1556.00/19).

b. The devices and circuits shall be certified for compliance with the applicable requirements of ASME A17.1-2013, section 2.26.4.3.2.

c. The access door or cover of the enclosures containing the SIL-rated components shall be clearly labeled or tagged on their exterior with the statement:

Assembly contains SIL-rated devices
Refer to Maintenance Control Program and
wiring diagrams prior to performing work

d. Unique maintenance procedures or methods required for the inspection, testing, or replacement of the SIL-rated circuits shall be developed and a copy maintained in the elevator machine/control room/space. The procedures or methods shall include clear color photographs of each SIL-rated component, with notations identifying parts and locations.

e. Wiring diagrams that include part identification, SIL, and certification information shall be maintained in the elevator machine/control room/space.

f. A successful test of the SIL-rated devices and circuits shall be conducted initially and not less than annually in accordance with the testing procedure. The test shall demonstrate that SIL-rated devices, safety functions, and related circuits operate as intended.

g. Any alterations to the SIL-rated devices and circuits shall be made in compliance with the Elevator Safety Orders. If the Elevator Safety Orders do not contain specific

provisions for the alteration of SIL-rated devices, the alterations shall be made in conformance with ASME A17.1-2013, section 8.7.1.9.

h. Any replacement of the SIL-rated devices and circuits shall be made in compliance with the Elevator Safety Orders. If the Elevator Safety Orders do not contain specific provisions for the replacement of SIL-rated devices, the replacement shall be made in conformance with ASME A17.1-2013, section 8.6.3.14.

i. Any repairs to the SIL-rated devices and circuits shall be made in compliance with the Elevator Safety Orders. If the Elevator Safety Orders do not contain specific provisions for the repair of SIL-rated devices, the repairs shall be made in conformance with ASME A17.1-2013, section 8.6.2.6.

j. Any space containing SIL-rated devices and circuits shall be maintained within the temperature and humidity range specified by Schindler Elevator Corporation. The temperature and humidity range shall be posted on each enclosure containing SIL-rated devices and circuits.

k. Field changes to the SIL-rated system are not permitted. Any changes to the SIL-rated system's devices and circuitry will require recertification and all necessary updates to the documentation and diagrams required by conditions d. and e. above.

6. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.

7. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way that the Applicant was required to notify them of the docketed application for permanent variance per California Code of Regulations, sections 411.2 and 411.3.

8. This Decision and Order shall remain in effect unless duly modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the procedural manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

Kelly Chau, Hearing Officer

DATED February 4, 2026

EXHIBIT 1
October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device's functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

EXHIBIT 2

Suspension Means – Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings. Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Pl., Suite 700, Santa Ana, CA 92707, Attn: Engineering section.

2. Each such report shall contain, but not necessarily be limited to, the following information:

    a. The State-issued conveyance number, complete address, and PERMANENT VARIANCE NO. file number that identifies the permanent variance.

    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).

    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.

    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.

    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.

    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.

    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.

    h. All information provided on the crosshead data plate per ASME Al7.l-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-491	UC Davis Health	UCD CUPx 4820 2nd Ave. Sacramento, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as

specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-492	The Open Door Network	529 Dolores St. Bakersfield, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each

Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-493	Perris Elementary School District	Skyview Elementary School - Bldg. G 625 Midred St. Perris, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

   (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:

   ...

   (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

   The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

   This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
   The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-494	Manteca Unified School District	Manteca High School - Bldg. L 450 E. Yosemite Ave. Manteca, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 29, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-495	RAR2-DEL AMO CROSSING OWNER, LLC	3863 Carson St. Torrance, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates and Wolter Geesink with Otis Elevator Company appeared on behalf of each Applicant; and Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

Kelly Chau, Hearing Officer

DATED: February 2, 2026

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-496	Meridian Family Apartments, L.P.	969 Meridian Ave. San Jose, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-498	The Hamid and Azita Yousefian Family Trust	1016 N. State St. Los Angeles, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-499	3636 4th Ave LLC.	3636 4th Ave. San Diego, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-500	Lawndale Elementary School District	Will Rogers Middle School 4110 154th St. Lawndale, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

   (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:

   ...

   (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

   The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

   This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
   The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-501	Liberation Park Residences, L.P.	2751 73rd Ave. Oakland, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-502	160 Freelon Housing Partners, L.P.	160 Freelon St. San Francisco, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-503	1634 20th Street, L.P.	1634 20th St. Santa Monica, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-504	Berendo QOZB LLC	1023 N. Berendo St. Los Angeles, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-505	BIF NON OZ 6200 Broadway BLK, LLC	6200 S. Broadway Los Angeles, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-506	Christ Presbyterian Church	36 E. Victoria Ave. Santa Barbara, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each

Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-507	City of Ontario	Vineyard Parking Structure 3201 S. Vineyard Ave. Ontario, CA	4

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-508	CoreLink-Scripps Holdings, LLC	Scripps College - Dance Building 248 E. 11th St. Claremont, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-509	CoreLink-Scripps Holdings, LLC	Scripps College – 10th St. Building 251 E. 10th St. Claremont, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-510	California State University San Marcos	Integrated Science & Engineering Building #36A 333 S. Twin Oaks Valley Rd. San Marcos, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table

PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the

subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance

record subject to ASME A17.1-2004, section 8.6.1.4).

f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

   a. The width and thickness in millimeters or inches;

   b. The manufacturer's rated breaking strength in (kN) or (lbf);

   c. The name of the person or organization that installed the flat coated steel belts;

   d. The month and year the flat coated steel belts were installed;

   e. The month and year the flat coated steel belts were first shortened;

   f. The name or trademark of the manufacturer of the flat coated steel belts; and

   g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

   a. The number of belts;

   b. The belt width and thickness in millimeters or inches; and

   c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

   a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

   b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

   c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

e. The applicant shall provide durable signs with lettering not less than ½ inch on a contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).

h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon request.

12. The speed governor rope and sheaves shall comply with the following:

    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.

    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.

    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:

    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.

    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.

15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.

16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.

17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.

18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives

are to be notified of docketed permanent variance applications.

19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-511	Formosa Bureau of Investments LLC.	5817 W. Virginia Ave. Los Angeles, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-512	Hope Apartments Owner, LLC,	1006 Carlsbad Village Dr. Carlsbad, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-513	LINC-Eureka APTS, LP	550 M St. Eureka, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-514	LINC-Eureka APTS, LP	611 8th St. Eureka, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-515	LINC-Eureka APTS, LP	1310 Myrtle Ave. Eureka, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-516	Marin County Pacific Associates LP	825 Drake Ave. Marin City, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-517	Millbrae Broadway Pacific Associates, LP, A California Limited Partnership	1301 Broadway Millbrae, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-518	QND LLC	11313-11315 Garvey Ave El Monte, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-519	Richman Oroville Senior Apartments, LP	3290 Lincoln Blvd. Oroville, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each

Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-520	Rise Carmel LP	350 Enterprise St. San Marcos, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-521	Sacramento 11th Street II, LP	815 11th St. Sacramento, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-522	San Jose South 1st Street Associates, a California Limited Partnership	802 S. 1st St. San Jose, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-523	San Francisco Airport	450 Upper Domestic Loop (C4C) San Francisco, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-524	Street Retail, LLC	Santana Row Lot 12 - Bldg A 358 Hatton St. San Jose, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-525	Street Retail, LLC	Santana Row Lot 12 - Bldg B 358 Hatton St. San Jose, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 30, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-526	SyRes Properties LLC	557 E. Bayshore Rd Redwood City, CA	4

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 31, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-528	Venice Cardiff, LLC	9431 W. Venice Blvd Culver City, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 31, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-529	Ventura Surgical, LLC	3212 Loma Vista Rd Ventura, CA	1

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, appeared on behalf of each Applicant; and David Morris appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application
PD4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top

railing is inset);

- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 31, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-530	Icon SSF Apartments Owner LLC	Alexan Icon - Building 2 1588 San Mateo Dr. South San Francisco, CA	3

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 31, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-531	County of Orange	Youth Transition Center 303 City Dr. South Orange, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

> (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:
>
> ...
>
> (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as

specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-532	JS IV View at San Bruno, LLC	Building A 850 W. San Bruno Ave. San Bruno, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 31, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-533	JS IV View at San Bruno, LLC	Building B 850 W. San Bruno Ave. San Bruno, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 31, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Medical Emergency Elevator Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-534	Lone Oak – Rancho, L.L.C.	Office and Mezzanine 10670 6th St. Rancho Cucamonga, CA	0

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact and Applicable Regulations

1. Applicant requests a permanent variance from section 3041, subdivision (e)(1)(C), which states:

   (1) All buildings and structures constructed after the effective date of this order that are provided with one or more passenger elevators shall be provided with not less than one passenger elevator designed and designated to accommodate the loading and transport of an ambulance gurney or stretcher maximum size 22 ½ in. (572 mm) by 75 in. (1.90 m) in its horizontal position and arranged to serve all landings in conformance with the following:

   ...

   (C) The elevator car shall have a minimum inside car platform of 80 in. (2.03 m) wide by 51 in. (1.30 m) deep.

   The intent of this language is to ensure that there is enough space to accommodate the access and egress of a gurney and medical personnel inside of a medical service elevator.

   This standard is made applicable to Group IV by section 3141.7, subdivision (b), which reads, "Elevators utilized to provide medical emergency service shall comply with Group II, section 3041(e)."

2. Applicant proposes to comply with the requirements of the 2019 California Building Code, section 3002.4.1a in the design of its medical emergency service elevator. That section requires:
   The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

   The purpose of this requirement is to ensure that an elevator designated for emergency medical service will accommodate a minimum of two emergency personnel with an ambulance gurney or stretcher.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A.1 table shall have permanent variances from sections 3041, subdivision (e)(1)(C) and 3141.7, subdivision (b) subject of the following conditions:

1. All medical emergency service elevator(s) shall comply with the requirements of the 2019 California Building Code section 3002.4.1a:

   > The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5-inch (127 mm) radius corners] in the horizontal, open position.

2. All medical emergency service elevator(s) shall be identified in the building construction documents in accordance with the 2019 California Building Code, section 3002.4a.
3. Dimensional drawings and other information necessary to demonstrate compliance with the conditions of this permanent variance decision shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).
4. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing the elevators shall be provided a copy of this variance decision.
5. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in service prior to the Permit to Operate being issued by Cal/OSHA.
6. Applicant shall notify its employees and their authorized representative, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to sections 411.2 and 411.3.
7. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in accordance with then in effect administrative procedures of the Board.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: February 2, 2026

Kelly Chau

Kelly Chau, Hearing Officer

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: Otis Gen2S/Gen3Edge/Gen3 Core Elevator & Medical Emergency Car Dimensions	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicants") below have applied for permanent variances from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations. Unless otherwise noted, all references in this matter are to the California Code of Regulations, title 8. The variance applications are as follows:

Permanent Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
25-V-535	Lone Oak – Rancho, L.L.C.	Parking Structure 10670 6th St. Rancho Cucamonga, CA	2

2. This proceeding is conducted in accordance with Labor Code section 143 and section 401, et seq. of the Occupational Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer Kelly Chau, both presiding and hearing the matter on its merit as a basis of proposed decision to be advanced to the Board for its consideration.

2. At the hearing, Dan Leacox, with Leacox & Associates, and Wolter Geesink with Otis Elevator Company, appeared on behalf of each Applicant; Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

Exhibit Number	Description of Exhibit
PD1	Application(s) for Permanent Variance per section A.1 table
PD2	OSHSB Notice of Hearing
PD3	Cal/OSHA Review of Variance Application

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Findings of Fact

1. Each Applicant intends to utilize Otis Gen3 Edge/Gen2S/Gen3 Core elevators at the locations and in the numbers stated in the above section A.1 table. Applicant may utilize the variance from minimum inside car platform dimensions for other elevators designated for emergency medical service at the same variance location.
2. The installation contracts for these elevators were or will be signed on or after May 1, 2008, making the elevators subject to the Group IV Elevator Safety Orders.
3. The Board incorporates by reference the relevant findings in previous Board decisions:
    a. Items D.3 through D.9 of the Proposed Decision adopted by the Board on July 18, 2013 for Permanent Variance No. 12-V-093;
    b. Item D.4 of the Proposed Decision adopted by the Board on September 25, 2014 for Permanent Variance No. 14-V-206;
    c. Item B of the Proposed Decision adopted by the Board on September 15, 2022 for Permanent Variance No. 22-V-302 regarding medical emergency car dimensions; and
    d. Items C and D of the Proposed Decision adopted by the Board on June 20, 2024 for Permanent Variance No. 24-V-193 regarding the Gen3 Core elevator equivalent safety.
4. Cal/OSHA, by way of written submissions to the record (Exhibit PD-3), and position stated at hearing, is of the well informed opinion that grant of requested permanent variance, as limited and conditioned per the below Decision and Order will provide employment, places of employment, and subject conveyances, as safe and healthful as would prevail given non-variant conformity with the Elevator Safety Order requirements from which variance has been requested.

D. Conclusive Findings

A preponderance of the evidence supports the finding that each Applicants' proposal, subject to all conditions and limitations set forth in the below Decision and Order, will provide equivalent safety and health to that which would prevail upon full compliance with the requirements of the Elevator Safety Orders from which variance is being sought.

E. Decision and Order

Each permanent variance application the subject of this proceeding is conditionally GRANTED as specified below, and to the extent, as of the date the Board adopts this Proposed Decision, each Applicant listed in the above section A table shall have permanent variances from the following sections of ASME A17.1-2004 that section 3141 makes applicable to the elevators the subject of those applications:

- **Car top railing**: sections 2.14.1.7.1 (to permit an inset car top railing, if, in fact, the car top railing is inset);
- **Speed governor over-speed switch**: 2.18.4.2.5(a) (to permit the use of the speed reducing system proposed by the Applicants, where the speed reducing switch resides in the controller algorithms, rather than on the governor, with the necessary speed input supplied by the main encoder signal from the motor);
- **Governor rope diameter**: 2.18.5.1 (to allow the use of reduced diameter governor rope);
- **Pitch diameter**: 2.18.7.4 (to permit the use of the speed-reducing system proposed by the Applicant, where the rope sheave pitch diameter is not less than 180 mm [7.1 in.]);
- **Suspension means**: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, 2.20.9.3.4 and 2.20.9.5.4—the variances from these "suspension means" provisions to permit the use of Otis Gen2 flat coated steel suspension belts in lieu of conventional steel suspension ropes;
- **Inspection transfer switch**: 2.26.1.4.4(a) (to allow the inspection transfer switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room); and
- **Seismic reset switch**: 8.4.10.1.1(a)(2)(b) (to allow the seismic reset switch to reside at a location other than a machine room, if, in fact, it does not reside in the machine room).
- **Minimum Inside Car Platform Dimensions**: 3041(e)(1)(C) and 3141.7(b) (to comply with the performance-based requirements of the 2019 California Building Code section 3002.4.1a)

These variances apply to the locations and numbers of elevators stated in the section A table (so long as the elevators are Gen3 Edge/Gen2S Group and Gen3 Core & Medical Emergency Elevator Car Dimensions (Group IV) that are designed, equipped, and installed in accordance with, and are otherwise consistent with, and are subject to the following conditions:

1. The suspension system shall comply with the following:
    a. The coated steel belt and connections shall have factors of safety equal to those permitted for use by section 3141 [ASME A17.1-2004, section 2.20.3] on wire rope suspended elevators.
    b. Steel coated belts that have been installed and used on another installation shall not be reused.
    c. The coated steel belt shall be fitted with a monitoring device which has been accepted by Cal/OSHA and which will automatically stop the car if the residual strength of any single belt drops below 60 percent. If the residual strength of any single belt drops below 60 percent, the device shall prevent the elevator from restarting after a normal stop at a landing.
    d. Upon initial inspection, the readings from the monitoring device shall be documented and submitted to Cal/OSHA.
    e. A successful test of the monitoring device's functionality shall be conducted at least once a year (the record of the annual test of the monitoring device shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    f. The coated steel belts used shall be accepted by Cal/OSHA.

2. With respect to each elevator subject to this variance, the applicant shall comply with Cal/OSHA Circular Letter E-10-04, the substance of which is attached hereto as Addendum 1 and incorporated herein by this reference.

3. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection, and testing of the belts and monitoring device and criteria for belt replacement, and the applicant shall make those procedures and criteria available to Cal/OSHA upon request.

4. The flat coated steel belts shall be provided with a metal data tag that is securely attached to one of those belts. This data tag shall bear the following flat steel coated belt data:

    a. The width and thickness in millimeters or inches;

    b. The manufacturer's rated breaking strength in (kN) or (lbf);

    c. The name of the person or organization that installed the flat coated steel belts;

    d. The month and year the flat coated steel belts were installed;

    e. The month and year the flat coated steel belts were first shortened;

    f. The name or trademark of the manufacturer of the flat coated steel belts; and

    g. Lubrication information.

5. There shall be a crosshead data plate of the sort required by section 2.20.2.1, and that plate shall bear the following flat steel coated belt data:

    a. The number of belts;

    b. The belt width and thickness in millimeters or inches; and

    c. The manufacturer's rated breaking strength per belt in (kN) or (lbf).

6. The opening to the hoistway shall be effectively barricaded when car top inspection, maintenance, servicing, or testing of elevator equipment in the hoistway is required. If service personnel must leave the area for any reason, the hoistway and control room doors shall be closed.

7. If there is an inset car top railing:

    a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to climb on railings to perform adjustment, maintenance, repairs or inspections. The applicant shall not permit anyone to stand on or climb over the car top railing.

    b. The distance that the car top railing may be inset shall be limited to no more than 6 inches.

    c. All exposed areas outside the car top railing shall preclude standing or placing objects or persons which may fall and shall be beveled from the mid- or top rail to the outside of the car top.

    d. The top of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4 inch diagonal red and white stripes.

    e. The applicant shall provide durable signs with lettering not less than ½ inch on a

contrasting background on each inset railing; each sign shall state:

CAUTION
DO NOT STAND ON OR CLIMB OVER RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing shall be measured from the car top and not from the required bevel).

8. If the seismic reset switch does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
9. If the inspection transfer switch required by ASME A17.1, rule 2.26.1.4.4(a) does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the inspection and test control panel located in one upper floor hoistway door jamb or in the control space (outside the hoistway) used by the motion controller.
10. When the inspection and testing panel is located in the hoistway door jamb, the inspection and test control panel shall be openable only by use of a Security Group I restricted key.
11. The governor speed-reducing switch function shall comply with the following:
    a. It shall be used only with direct drive machines; i.e., no gear reduction is permitted between the drive motor and the suspension means.
    b. The velocity encoder shall be coupled to the driving machine motor shaft. The “C” channel of the encoder shall be utilized for velocity measurements required by the speed reducing system. The signal from “C” channel of the encoder shall be verified with the “A” and “B” channels for failure. If a failure is detected then an emergency stop shall be initiated.
    c. Control system parameters utilized in the speed-reducing system shall be held in non-volatile memory.
    d. It shall be used in conjunction with approved car-mounted speed governors only.
    e. It shall be used in conjunction with an effective traction monitoring system that detects a loss of traction between the driving sheave and the suspension means. If a loss of traction is detected, then an emergency stop shall be initiated.
    f. A successful test of the speed-reducing switch system’s functionality shall be conducted at least once a year (the record of the annual test of the speed-reducing switch system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    g. A successful test of the traction monitoring system’s functionality shall be conducted at least once a year (the record of the annual test of the traction monitoring system shall be a maintenance record subject to ASME A17.1-2004, section 8.6.1.4).
    h. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the maintenance, inspection, and testing of the speed-reducing switch and traction monitoring systems. The Applicant shall make the procedures available to Cal/OSHA upon

request.

12. The speed governor rope and sheaves shall comply with the following:
    a. The governor shall be used in conjunction with a 6 mm (0.25 in.) diameter steel governor rope with 6-strand, regular lay construction.
    b. The governor rope shall have a factor of safety of 8 or greater as related to the strength necessary to activate the safety.
    c. The governor sheaves shall have a pitch diameter of not less than 180 mm (7.1 in.).

13. All medical emergency service elevators shall comply with the following:
    a. The requirements of the 2019 California Building Code (CBC), section 3002.4.1a;

    The medical emergency service elevator shall accommodate the loading and transport of two emergency personnel, each requiring a minimum clear 21-inch (533 mm) diameter circular area and an ambulance gurney or stretcher [minimum size 24 inches by 84 inches (610 mm by 2134 mm) with not less than 5inch (127 mm) radius corners] in the horizontal, open position.

    b. All medical emergency service elevators shall be identified in the building construction documents in accordance with the 2019 CBC, section 3002.4a.
    c. Dimensional drawings and other information necessary to demonstrate compliance with these conditions shall be provided to Cal/OSHA, at the time of inspection, for all medical emergency service elevator(s).

14. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by Certified Competent Conveyance Mechanics who have been trained to, and are competent to, perform those tasks on the Gen3 Edge/Gen2S/Gen3 Core elevator system in accordance with the written procedures and criteria required by Condition No. 3 and in accordance with the terms of this permanent variance.
15. Any Certified Qualified Conveyance Company performing inspections, maintenance, servicing, or testing of the elevators shall be provided a copy of this variance decision.
16. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and a Permit to Operate shall be issued before the elevator is placed in service.
17. The Applicant shall be subject to the Suspension Means – Replacement Reporting Condition stated in Addendum 2, as hereby incorporated by this reference.
18. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications.
19. This Decision and Order shall remain in effect unless modified or revoked upon application by the Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in

accordance with the Board's procedural regulations at section 426, subdivision (b).

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 31, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

October 6, 2010

CIRCULAR LETTER E-10-04

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device’s functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQS

ADDENDUM 2

Suspension Means - Replacement Reporting Condition

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

1. A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, 2 MacArthur Place, Suite 700, Santa Ana, CA 92707, Attn: Engineering section.
2. Each such report shall contain, but not necessarily be limited to, the following information:
    a. The State-issued conveyance number, complete address, and Permanent Variance number that identifies the permanent variance.
    b. The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).
    c. The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.
    d. The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, certification expiration date, and signature of each CCCM performing the replacement work.
    e. The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.
    f. A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.
    g. A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.
    h. All information provided on the crosshead data plate per ASME A17.1-2004, section 2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.
    i. For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is

modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

j. For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

k. Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

3. In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2a above.

BEFORE THE
OCCUPATIONAL SAFETY AND HEALTH STANDARDS BOARD
DEPARTMENT OF INDUSTRIAL RELATIONS
STATE OF CALIFORNIA

In the Matter of Application for Permanent Variance Regarding: TK Elevator EOX MRL	Permanent Variance No: See section A.1 table below **PROPOSED DECISION** Hearing Date: January 21, 2026 Location: Zoom

A. Subject Matter

1. The applicants ("Applicant") below have applied for permanent variance from provisions of the Elevator Safety Orders, found at title 8 of the California Code of Regulations[1], as follows:

Variance No.	Applicant Name	Variance Location Address	No. of Conveyances
26-V-001	SHP Castro LLC	747 W. Dana St. Mountain View, CA	1

2. These proceedings are conducted in accordance with Labor Code section 143, and section 401, et seq. of the Occupation Safety and Health Standards Board's ("Board" or "OSHSB") procedural regulations.

B. Procedural

1. This hearing was held on January 21, 2026 via videoconference by the Board with Hearing Officer, Kelly Chau, presiding and hearing the matter on its merit in accordance with section 426.

2. At the hearing, James Day with TK Elevator, appeared on behalf of the Applicant. Jose Ceja and Mark Wickens appeared on behalf of the Division of Occupational Safety and Health ("Cal/OSHA").

3. Documentary and oral evidence was received at the hearing, and by stipulation of all parties, documents were admitted into evidence:

[1] Unless otherwise noted, references are to the California Code of Regulations, title 8.

Exhibit Number	Description of Exhibit
PD-1	Application(s) for Permanent Variance per section A.1 table
PD-2	OSHSB Notice of Hearing
PD-3	Cal/OSHA Review of Variance Application
PD-4	Review Draft-1 Proposed Decision

4. Official notice is taken of the Board's files, records, recordings and decisions concerning the Elevator Safety Order requirements from which variance shall issue. On January 21, 2026, the hearing and record closed, and the matter was taken under submission by the Hearing Officer.

C. Relevant Safety Orders

Car Top Railings (ASME A17.1-2004, section 2.14.1.7.1)

Section 3141[ASME A17.1-2004, Section 2.14.1.7.1] states:

"2.14.1.7.1 A standard railing conforming to 2.10.2 shall be provided on the outside perimeter of the car top on all sides where the perpendicular distance between the edges of the car top and the adjacent hoistway enclosure exceeds 300 mm (12 in.) horizontal clearance."

The intent of ASME A17.1-2004, section 2.14.1.7.1 requirement is to provide fall protection to a potentially hazardous condition. The code requires these railings to be installed at the perimeter of the car to prevent people or objects from occupying the area beyond them.

ASME A17.1-2019, 2.14.1.7.1 Railing and Equipment on Car Enclosure Top states:

"**2.14.1.7.1** A standard railing conforming to 2.10.2 shall be provided on the outside perimeter of the car enclosure top on all sides where a 300 mm (12 in.) ball can pass between the edges of the car enclosure top and the adjacent hoistway enclosure and on sides where there is no hoistway enclosure. If clearances require **(see 2.14.1.7.2)** the standard railing to be located more than 100 mm (4 in.) from the edge of the outside perimeter of the car enclosure top, the top of the car enclosure outside of the railing shall be clearly marked. The marking shall consist of alternating 100 mm (4 in.) diagonal red and white stripes. The forces specified in 2.10.2.4 shall not deflect the railing beyond the perimeter of the car top. The top-of-car enclosure, or other surface specified by the elevator installer, shall be the working surface referred to in 2.10.2.".

Suspension Means

(ASME A17.1-2004, section 2.20.1)

2.20.1 Suspension Means

Elevator cars shall be suspended by steel wire ropes attached to the car frame or passing around sheaves attached to the car frame specified in 2.15.1. Ropes that have previously been installed and used on another installation shall not be reused.

Only iron (low-carbon steel) or steel wire ropes, having the commercial classification "Elevator Wire Rope," or wire rope specifically constructed for elevator use, shall be used for the suspension of elevator cars and for the suspension of counterweights. The wire material for ropes shall be manufactured by the open-hearth or electric furnace process or their equivalent.

(ASME A17.1-2004, section 2.20.2.])

2.20.2.1 On Crosshead Data Plate.

The crosshead data plate required by 2.16.3 shall bear the following wire-rope data:

(a) the number of ropes

(b) the diameter in millimeters (mm) or inches (in.)

(c) the manufacturer's rated breaking strength per rope in kilo Newton (kN) or pounds (lb)

(ASME A17.1-2004, section 2.20.2.2)

2.20.2.2 On Rope Data Tag.

A metal data tag shall be securely attached to one of the wire-rope fastenings. This data tag shall bear the following wire-rope data:

(a) the diameter in millimeters (mm) or inches (in.)

[…]

(f) whether the ropes were nonpreformed or preformed

[…]

(ASME A17.1-2004, section 2.20.3)

2.20.3 Factor of Safety

The factor of safety of the suspension wire ropes shall be not less than shown in Table 2.20.3. Figure 8.2.7 gives the minimum factor of safety for intermediate rope speeds. The factor of safety shall be based on the actual rope speed corresponding to the rated speed of the car.

The factor of safety shall be calculated by the following formula:

$$f = \frac{S \times N}{W}$$

where

N = number of runs of rope under load. For 2:1 roping, N shall be two times the number of ropes used, etc.

S = manufacturer's rated breaking strength of one rope

W = maximum static load imposed on all car ropes with the car and its rated load at any position in the hoistway

(ASME A17.1-2004, section 2.20.4)

2.20.4 Minimum Number and Diameter of Suspension Ropes

The minimum number of hoisting ropes used shall be three for traction elevators and two for drum-type elevators.

Where a car counterweight is used, the number of counterweight ropes used shall be not less than two.

The term" diameter," where used in reference to ropes, shall refer to the nominal diameter as given by the rope manufacturer.

The minimum diameter of hoisting and counterweight ropes shall be 9.5 mm (0.375 in.). Outer wires of the ropes shall be not less than 0.56 mm (0.024 in.) in diameter.

(ASME A17.1-2004, section 2.20.9[.1])

2.20.9 Suspension-Rope Fastening

2.20.9.1 Type of Rope Fastenings. The car and counterweight ends of suspension wire ropes, or the stationary hitch-ends where multiple roping is used, shall be fastened in such a manner that all portions of the rope, except the portion inside the rope sockets, shall be readily visible.

Fastening shall be

(a) by individual tapered rope sockets (see 2.20.9.4) or other types of rope fastenings that have undergone adequate tensile engineering tests, provided that

(1) such fastenings conform to 2.20.9.2 and 2.20.9.3;

(2) the rope socketing is such as to develop at least 80% of the ultimate breaking

strength of the strongest rope to be used in such fastenings; or

(b) by individual wedge rope sockets (see 2.20.9.5); and

(c) U-bolt-type rope clamps or similar devices shall not be used for suspension rope fastenings.

Software-Controlled Means to Remove Power from Driving Machine

(ASME A17.1-2004, section 2.26.9.4)

ASME A17.1-2004 allows the use of software systems to provide redundancy, provided that the removal of power from the driving machine and brake is not done by using only a software-controlled means.

Section 3141**[ASME A17.1-2004, Section 2.26.9.4]** states:

*"**2.26.9.4** Redundant devices used to satisfy 2.26.9.3 in the determination of the occurrence of a single ground, or the failure of any single magnetically operated switch, contactor or relay, or of any single solid state device, or any single device that limits the leveling or truck zone, or a software system failure, shall be checked prior to each start of the elevator from a landing, when on automatic operation. When a single ground or failure, as specified in 2.26.9.3, occurs, the car shall not be permitted to restart. Implementation of redundancy by a software system is permitted, provided that the removal of power from the driving-machine motor and brake shall not be solely dependent on software-controlled means."*

The intent of the relevant portion of ASME A17.1-2004 section 2.26.9.4 requirement is to address hazards associated with exclusive reliance on software to remove power from the elevator's driving machine when device or circuit failure is detected (see ASME A17.1-2004, section 2.26.9.3).

More recent editions of ASME A17.1 have recognized that systems that have undergone extensive evaluation, testing, and certification processes can achieve equivalent or superior safety outcomes. More recent editions of ASME A17.1 contain requirements that govern the certification and use of these SIL-rated circuits, software, and devices.

SIL-Rated System to Inhibit Current Flow to Alternating Current (AC) Drive Motor

(ASME A17.1-2004, section 2.26.9.6.1)

2.26.9.6.1 Two separate means shall be provided to independently inhibit the flow of alternating-current through the solid state devices that connect the direct-current power source to the alternating-current driving motor. At least one of the means shall be an electromechanical relay.

More recent editions of ASME A17.1 have recognized that systems that have undergone extensive evaluation, testing, and certification processes can achieve equivalent or superior safety outcomes. More recent editions of ASME A17.1 contain requirements that govern the certification and use of these SIL-rated circuits, software, and devices.

Inspection Transfer Switch

(ASME A17.1-2004, section 2.26.1.4.4 (a))

2.26.1.4.4 Machine Room Inspection Operation

(a) When machine room inspection operation is provided, it shall conform to 2.26.1.4.1, and the transfer switch shall be located in the machine room.

The intent of ASME A17.1-2004, section 2.26.1.4.4(a) requirement is to ensure that the inspection transfer switch is conveniently accessible to the mechanic and resides in a secure location (machine room).

Seismic Reset Switch

(ASME A17.1-2004, section 8.4.10.1.1(a)(2)(b))

8.4.10.1.1 Earthquake Equipment (See Also Fig. 8.4.10.1.1)

(a) All traction elevators operating at a rated speed of 0.75 m/s (150 ft/min) or more and having counterweights located in the same hoistway shall be provided with the following:

(1) seismic zone 3 or greater: a minimum of one seismic switch per building

(2) seismic zone 2 or greater:

(a) a displacement switch for each elevator

(b) an identified momentary reset button or switch for each elevator, located in the control panel in the elevator machine room [see 8.4.10.1.3(i)]

D. Findings of Fact

1 The Application asserts:

> "The applicant, through TK Elevator (TKE), is proposing to install a standard railing on the car top and believes equivalent or superior safety is achieved by complying with ASME A17.1-**2019**, 2.14.1.7.1. This standard allows the railing to be in-set in order to create a space around

the top rail to provide greater clearances when the hand is placed on the rail. The EOX standard rail is-inset approximately 3.75 inches. TKE will bevel any area of exposed cartop outside the standard rail greater than 4". By meeting the requirements in ASME A17.1-2019 and any additional beveling is how the applicant believes equivalent or superior safety is achieved".

2. The Cal/OSHA evaluation notes that the Applicant has omitted reference to "(see 2.14.1.7.2)", in the ASME A17.1 2019 above from their application. This reference contains vertical clearance requirements that would be in conflict with the current ESO (ASME A171.1-2004, section 2.4.6.2).

3. Cal/OSHA notes, in previous OSHSB Decisions, where car top railings require in-setting from the outside perimeter of the car top enclosure, the OSHSB has ruled that:

> *"All exposed areas of the car top outside the car top railing where the distance from the railing to the edge of the car top exceeds **2 inches**, shall be beveled with metal, at an angle not less than 75 degrees with the horizontal, from the mid or top rail to the outside of the car top, **such that no person or object can stand, sit, kneel, rest, or be placed in the exposed areas**." (Reference OSHSB File No. 15-V-349, G. Decision and Order, Paragraph 29, Page 39 of 41, Permanent Variance No. 18-V-364, D. Decision and Order, Condition 1.3)*

4. Cal/OSHA does not believe that the Applicant's proposed exclusive compliance with ASME A17.1-**2019** section 2.14.1.7.1 provides equivalent safety to conditions and intentions that have been established in the similar proceeding matters referenced above.

5. Cal/OSHA believes that in-setting of the car top railing as proposed by the Applicant, along with the Recommended Conditions below, provides equivalent safety.

6. Applicant proposes to utilize noncircular elastomeric-coated steel belts ("ECSBs") rather than steel ropes in a machine room-less ("MRL") elevator installation, with updated data plates, data tags, and wedge sockets designed for use with ECSBs, as well as the appropriate factor of safety criteria conforming to ASME 17.1-2019, with a continuous residual strength detection device ("RSDD") compliant with the *San Francisco Public Works (Permanent Variance No. 21-V-061, et al.)* decisions.

7. The Applicant intends to utilize an engineered belt-type suspension product (ECSB) that arranges steel tension members longitudinally in an elastomeric coating using specifically designed fastenings for attachment. The Applicant asserts that the proposed ECSB suspension complies with the more recent edition of ASME A17.1-2019, which contains specific requirements for this type of suspension means. The Applicant asserts that proposed suspension means provides equivalent safety through compliance with the provisions contained in ASME A17.1-2019, ASME A17.6-2017 and the following:
    a. Belt tension monitoring.
    b. Slack belt detection (Broken suspension)
    c. Slip detection (traction loss)

d. Factor of safety in accordance with the code.
e. Residual Strength Detection Device (RSDD) accepted by the Division.
f. Visual inspections of the suspension elements at 6 months, and annually thereafter.
g. Maintain manufacturer's quality control in accordance with ASME A17.6-2017 section 3.6.

8. Cal/OSHA believes the Applicant's proposal to utilize ECSB suspension with a functioning RSDD, along with the Recommended Conditions below, provides equivalent safety.

9. The Board has previously granted a permanent variance to a similar ECSB suspension systems. (See Permanent Variance No. 24-V-483)

10. The Applicant proposes the use of SIL-rated software and circuits to direct the removal of power to the elevator's driving machine. The Applicant asserts that their SIL-rated software and circuits meet the requirements of ASME A17.1-2019, section 2.26.9, for the use of SIL-rated systems in this role, providing equivalent safety to the existing ESO.

11. The Board has previously granted permanent variances permitting a similar use of a SIL-rated circuitry to meet this code requirement (Permanent Variance No. 24-V-483).

12. The Applicant asserts that equivalent safety is attained by relocating the inspection transfer switch to the "Control Room". Newer standards define spaces and rooms beyond a machine room (Machine Space, Control Space, etc.). The applicant through TKE believes equivalent safety is achieved by complying with the requirements in ASME A17.1-2019 section 2.26.1.4. machine rooms control rooms and control spaces are secured by a Group 1 security key, which would limit access to elevator personnel only.

13. The Standards Board has granted a permanent variance granting a similar switch relocation (see OSHSB File No. 24-V-483).

14. The Applicant asserts that equivalent safety is attained by relocating the seismic reset switch to the Machine Room, Control Room, or Control Space within the elevator's controller in accordance with ASME A17.1-2019 section 8.4.10.1.1(d). Machine rooms Control Rooms and Control spaces are secured by a Group 1 security key, which would limit access to elevator personnel only.

15. The Board has granted a permanent variance granting a similar switch relocation (see Permanent Variance No. 24-V-483).

16. The installation shall utilize the TK Elevator Model EOX MRL, a newly introduced elevator product with features similar to the EOX MRL(104DP001 RSDD, accepted by

Cal/OSHA on May 4, 2021).

E. Decision and Order

Applicant is hereby conditionally GRANTED Permanent Variance as specified below, and to the limited extent, as of the date the Board adopts this Proposed Decision, with respect to the section A specified number of TKE EOX elevator(s), at the specified location, each shall conditionally hold permanent variance from the following subparts of ASME A17.1-2004, currently incorporated by reference into section 3141 of the Elevator Safety Orders:

- Car-Top Railing: 2.14.1.7.1 (Limited to the extent necessary to permit the use of an inset car-top railing)
- Suspension Means: 2.20.1, 2.20.2.1, 2.20.2.2(a), 2.20.2.2(f), 2.20.3, 2.20.4, and 2.20.9.1 (Limited to the extent necessary to permit the use of the elastomeric-coated steel belts in lieu of circular steel suspension ropes)
- Inspection transfer switch: 2.26.1.4.4(a) (Limited to the extent necessary to permit the inspection transfer switch to reside at a location other than the machine room)
- Software Reliant Means to Remove Power: 2.26.9.4 (Limited to the extent necessary to permit the exclusive use of SIL-rated software systems as a means to remove power from the driving machine motor and brake)
- SIL-Rated Circuitry to Inhibit Current Flow: 2.26.9.6.1 (Limited to the extent necessary to permit the use of SIL-rated circuitry in place of an electromechanical relay to inhibit current flow to the drive motor)
- Seismic reset switch: 8.4.10.1.1(a)(2)(b) (Limited to the extent necessary to permit the seismic reset switch to reside at a location other than the machine room)

Recommended Conditions:

Inset Car Top Railing

1. Any and all inset car top railings shall comply with the following:

a. Serviceable equipment shall be positioned so that mechanics and inspectors do not have to stand on or climb over the railings to perform adjustments, maintenance, repairs or inspections. The Applicant shall not permit trained elevator mechanics or elevator service personnel to stand or climb over the car top railing.

b. The distance that the railing can be inset shall be limited to not more than six inches (6”).

c. All exposed areas of the car top outside the car top railing where the distance from the railing to the edge of the car top exceeds two inches (2”), shall be beveled with metal, at an angle of not less than 75 degrees with the horizontal, from the mid or top rail to the outside of the car top, such that no person or object can stand, sit, kneel, rest, or be placed in the exposed areas.

d. The top surface of the beveled area and/or car top outside the railing, shall be clearly marked. The markings shall consist of alternating 4” diagonal red and white stripes.

e. The Applicant shall provide durable signs with lettering not less than 1/2 inch on a contrasting background on each inset railing; each sign shall state:

CAUTION
STAY INSIDE RAILING
NO LEANING BEYOND RAILING
NO STEPPING ON, OR BEYOND, RAILING

f. The Group IV requirements for car top clearances shall be maintained (car top clearances outside the railing will be measured from the car top and not from the required bevel).

Suspension Means

2. The elevator suspension system shall comply with the following:

a. The elastomeric coated steel belts (ECSBs) and their associated fastenings shall conform to the applicable requirements of ASME A17.1-2019, sections:

2.20.4.3 – Minimum Number of Suspension Members
2.20.3 – Factor of Safety
2.20.9 – Suspension Member Fastening

b. Additionally, ECSBs shall meet or exceed all requirements of ASME A17.6 2010, Standard for Elevator Suspension, Compensation, and Governor Systems, Part 3 Noncircular Elastomeric Coated Steel Suspension Members for Elevators.

c. The Applicant shall not utilize the elevator unless the manufacturer has written procedures for the installation, maintenance, inspection and testing of the ECSBs and fastenings and related monitoring and detection systems and criteria for ECSB replacement, and the Applicant shall make those procedures and criteria available to the Certified Competent Conveyance Mechanic (CCCM) at the location of the elevator, and to Cal/OSHA upon request.

ECSB mandatory replacement criteria shall include:

i. Any exposed wire, strand or cord;

ii. Any wire, strand or cord breaks through the elastomeric coating;

iii. Any evidence of rouging (steel tension element corrosion) on any part of the elastomeric coated steel suspension member;

iv. Any deformation in the elastomeric suspension member such as, but not limited to, kinks or bends.

d. Traction drive sheaves must have a minimum diameter of 112 mm. The maximum speed of ECSBs running on 112 mm drive sheaves shall be no greater than 6.1 m/s.

e. If any one (1) ECSB needs replacement, the complete set of suspension members on the elevator shall be replaced. Exception: If a new suspension member is damaged during installation, and prior to any contemporaneously installed ECSB having been placed into service, it is permissible to replace the individual damaged suspension member. ECSBs that have been installed on another installation shall not be re used.

f. A traction loss detection means shall be provided that conforms to the requirements of ASME A17.1-2019, section 2.20.8.1. The means shall be tested for correct function annually in accordance with ASME A17.1-2019 section 8.6.4.19.12.

g. A broken suspension member detection means shall be provided that conforms to the requirements of ASME A17.1-2019, section 2.20.8.2. The means shall be tested for correct function annually in accordance with ASME A17.1-2019, section 8.6.4.19.13(a).

h. An elevator controller integrated bend cycle monitoring system shall monitor actual ECSB bend cycles, by means of continuously counting, and storing in nonvolatile memory, the number of trips that the ECSB makes traveling, and thereby being bent, over the elevator sheaves. The bend cycle limit monitoring means shall automatically stop the car normally at the next available landing before the bend cycle correlated residual strength of any single ECSB member drops below (60%) sixty percent of full rated strength. The monitoring means shall prevent the car from restarting. Notwithstanding any less frequent periodic testing requirement per Addendum 2 (Cal/OSHA Circular Letter), the bend cycle monitoring system shall be tested semiannually in accordance with the procedures required per above Conditions 2b above.

i. The elevator shall be equipped with a device to monitor the remaining residual strength of each ECSB. The device shall conform to the requirements of Cal/OSHA Circular Letter E-10-04, a copy of which is attached hereto as Exhibit 1 and incorporated herein by reference.

j. The elevator crosshead data plate shall comply with the requirements of ASME A17.1-201, section 2.20.2.1.

j. A suspension means data tag shall be provided that complies with the requirements

of ASME A17.1-2019, section 2.20.2.2.

k. Comprehensive visual inspections of the entire length of each and all installed suspension members, in conformity with above Conditions 2.3 and 2.4 specified criteria, shall be conducted and documented every six (6) months by a CCCM.

l. The Applicant shall be subject to the requirements per hereto attached, and inhere incorporated, Addendum 1, "Suspension Means Replacement Reporting Condition."

m Records of all tests and inspections shall be maintenance records subject to ASME A17.1-2004, sections 8.6.1.2, and 8.6.1.4, respectively.

n. The subject elevators(s) shall be equipped with a TK Elevator Model 104DP001 Residual Strength Detection Device accepted by Cal/OSHA on May 4, 2021 or Cal/OSHA accepted equivalent device.

Control and Operating Circuits
Combined Software Redundant Devices with Software Removal of Power from Driving Motor and Brake

Removal of Power from Driving Motor Without Electro-mechanical Switches

3. The SIL rated circuitry used to provide device/circuit redundancy and to inhibit electrical current flow in accordance with ASME A17.1-2004, sections 2.26.9.4 and 2.26.9.6.1 shall comply with the following:

a. The driving-machine motor control system shall consist of a TKE, model HVI-22 HW, High Voltage Inverter containing a Safe Torque Off printed circuit board assembly (STO). The STO shall be labeled or marked with a SIL rating (not less than SIL 3), the name or mark of the certifying organization and the SIL certification number FS/71/220, followed by the applicable revision number (as in FS/71/220/23/1060).

b. The software system and related circuits shall be certified for compliance with the applicable requirements of ASME A17.1-2019 Section 2.26.9.3.2(b), 2.26.4.3.2, 2.26.9.6.1(b) and 2.26.9.4.

c. The access door or cover of the enclosures containing the SIL-rated components shall be clearly labeled or tagged on their exterior with the statement:

d. The software system and related circuits shall be certified for compliance with

the applicable requirements of ASME A17.1-2019, section 2.26.4.3.2.

e. The access door or cover of the enclosures containing the SIL rated components shall be clearly labeled or tagged on their exterior with the statement:

Assembly contains SIL rated devices.
Refer to maintenance Control Program and wiring diagrams
prior to performing work.

f. Unique maintenance procedures or methods required for the inspection, testing, or replacement of the SIL rated circuits shall be developed and a copy maintained in the elevator machine/control room/space. The procedures or methods shall include clear color photographs of each SIL rated component, with notations identifying parts and locations.

g. Wiring diagrams that include part identification, SIL, and certification information shall be maintained in the elevator machine/control room/space.

h. A successful test of the SIL rated circuits shall be conducted initially and not less than annually in accordance with the testing procedure. The test shall demonstrate that SIL rated devices, safety functions, and related circuits operate as intended.

i. Any alterations to the SIL rated circuits shall be made in compliance with the Elevator Safety Orders. If the Elevator Safety Orders do not contain specific provisions for the alteration of SIL rated devices, the alterations shall be made in conformance with ASME A17.1-2019, section 8.7.1.9.

j. Any replacement of the SIL rated circuits shall be made in compliance with the Elevator Safety Orders. If the Elevator Safety Orders do not contain specific provisions for the replacement of SIL rated devices, the replacement shall be made in conformance with ASME A17.1-2019, section 8.6.3.14.

k. Any repairs to the SIL rated circuits shall be made in compliance with the Elevator Safety Orders. If the Elevator Safety Orders do not contain specific provisions for the repair of SIL rated devices, the repairs shall be made in conformance with ASME A17.1-2019, section 8.6.2.6.

l. Any space containing SIL rated circuits shall be maintained within the temperature and humidity range specified by TKE. The temperature and humidity range shall be posted on each enclosure containing SIL rated software or circuits.

m. Field software changes to the SIL rated system are not permitted. Any changes to the SIL rated system's circuitry will require recertification and all necessary updates to the documentation and diagrams required by Conditions 3.4 and 3.5 above.

Inspection Transfer Switch and Seismic Reset Switch

4. Inspection Transfer switch and Seismic Reset switch placement and enclosure shall comply with the following:

a. If the inspection transfer switch required by ASME A17.1-2004, section 2.26.1.4.4, does not reside in a machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the control/machinery room/space containing the elevator's control equipment in an enclosure secured by a lock openable by a Group 1 security key. The enclosure is to remain locked at all times when not in use.

b. If the seismic reset switch does not reside in the machine room, that switch shall not reside in the elevator hoistway. The switch shall reside in the control/machinery room/space containing the elevator's control equipment in an enclosure secured by a lock openable by a Group 1 security key. The enclosure is to remain locked at all times when not in use.

5. The elevator shall be serviced, maintained, adjusted, tested, and inspected only by CCCM having been trained, and competent, to perform those tasks on the TKE EVO 200 elevator system in accordance with written procedures and criteria, including as required per above Conditions 2.3, and 2.4.

6. Cal/OSHA shall be notified when the elevator is ready for inspection. The elevator shall be inspected by Cal/OSHA, and all applicable requirements met, including conditions of this permanent variance, prior to a Permit to Operate the elevator being issued. The elevator shall not be placed in full service prior to the Permit to Operate being issued by Cal/OSHA.

7. The Applicant shall notify its employees or their authorized representative(s), or both, of this order in the same way and to the same extent that employees and authorized representatives are to be notified of docketed permanent variance applications pursuant to California Code of Regulations, sections 411.2, and 411.3.

8. This Decision and Order shall remain in effect unless duly modified or revoked upon application by Applicant, affected employee(s), Cal/OSHA, or by the Board on its own motion, in the procedural manner prescribed.

Pursuant to section 426(b), the Proposed Decision is submitted to the Board for consideration of adoption.

DATED: January 27, 2026

Kelly Chau, Hearing Officer

ADDENDUM 1

SUSPENSION MEANS REPLACEMENT REPORTING REQUIREMENTS

Beginning on the date the Board adopts this Proposed Decision and continuing for a period of two years, the Applicant shall report to Cal/OSHA within 30 days any and all replacement activity performed on the elevator(s) pursuant to the requirements of ASME A17.1-2004, section 8.6.3 involving the suspension means or suspension means fastenings.

Further:

(1) A separate report for each elevator shall be submitted, in a manner acceptable to Cal/OSHA, to the following address (or to such other address as Cal/OSHA might specify in the future): Cal/OSHA Elevator Unit, Attn: Engineering section, 2 MacArthur Place Suite 700, Santa Ana, CA 92707.

(2) Each such report shall contain, but not necessarily be limited to, the following information:

(a) The State-issued conveyance number, complete address, and Permanent Variance file number that identifies the permanent variance.

(b) The business name, complete address, telephone number, and contact person of the elevator responsible party (presumably the Applicant or the subsequent holder of this variance).

(c) The business name, complete address, telephone number, and Certified Qualified Conveyance Company (CQCC) certification number of the firm performing the replacement work.

(d) The name (as listed on certification), Certified Competent Conveyance Mechanic (CCCM) certification number, and certification expiration date of each CCCM performing the replacement work.

(e) The date and time the elevator was removed from normal service for suspension replacement, the date and time the replacement work commenced, the date and time the replacement work was completed, and the date and time the elevator was returned to normal service.

(f) A detailed description of, and clear color photographs depicting, (1) all the conditions that existed in the suspension components requiring their replacement and (2) any conditions that existed to cause damage or distress to the suspension components being replaced.

(g) A detailed list of all elevator components adjusted, repaired, or replaced in conjunction with the suspension component replacement.

(h) All information provided on the crosshead data plate per ASME A17.1-2004, section

2.20.2.1, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

(i) For the suspension means being replaced, all information provided on the data tag required per ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

(j) For the replacement suspension means, all information provided on the data tag required by ASME A17.1-2004, section 2.20.2.2, unless that ASME requirement is modified by the conditions of a variance that pertains to the elevator in question, in which case, the information to be reported shall be the information required by the ASME provision as modified by the variance.

(k) Any other information requested by Cal/OSHA regarding the replacement of the suspension means or fastenings.

In addition to the submission of the report to Cal/OSHA, the findings of any testing, failure analysis, or other engineering evaluations performed on any portion of the replaced suspension components, or other elevator components replaced in conjunction therewith, shall be submitted to Cal/OSHA referencing the information contained in item 2(a) above.

ADDENDUM 2

CIRCULAR LETTER E-10-04, October 6, 2010

TO: Installers, Manufacturers of Conveyances and Related Equipment and, Other Interested Parties

SUBJECT: Coated Steel Belt Monitoring

The Elevator Safety Orders require routine inspection of the suspension means of an elevator to assure its safe operation.

The California Labor Code section 7318 allows Cal/OSHA to promulgate special safety orders in the absence of regulation.

As it is not possible to see the steel cable suspension means of a Coated Steel Belt, a monitoring device which has been accepted by Cal/OSHA is required on all Coated Steel Belts which will automatically stop the car if the residual strength of any belt drops below 60%. The Device shall prevent the elevator from restarting after a normal stop at a landing.

The monitoring device must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room. The removed device must be replaced or returned to proper service within 30 days.

If upon routine inspection, the monitoring device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room.

If upon inspection by Cal/OSHA, the monitoring device is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service.

If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

A successful test of the device's functionality shall be conducted once a year.

This circular does not preempt Cal/OSHA from adopting regulations in the future, which may address the monitoring of Coated Steel Belts or any other suspension means.

This circular does not create an obligation on the part of Cal/OSHA to permit new conveyances utilizing Coated Steel Belts.

Debra Tudor
Principal Engineer
Cal/OSHA-Elevator Unit HQ

ADDENDUM 3

(A) A Residual Strength Detection Device (RSDD) shall continuously monitor all Elastomeric Coated Steel Belt suspension members (ECSB), automatically stopping the car if the residual strength of any belt drops below 60%. The RSDD shall prevent the elevator from restarting after a normal stop at a landing. The RSDD shall device shall apply a form of electrical current and/or signal through the entire length of the steel tension elements of the ECSB and measure the current and/or signal on its return. The values measured shall be continuously compared to values that have been correlated to the remaining residual strength of the ECSB through testing. The required RSDD shall not rely upon giant magnetoresistance technology, or other magnetic measurement means, for residual strength detection or monitoring.

The RSDD must be properly installed and functional. A functioning device may be removed only after a determination has been made that the residual strength of each belt exceeds 60%. These findings and the date of removal are to be conspicuously documented in the elevator machine room or controller location. The removed RSDD must be replaced or returned to proper service within 30 days. If upon routine inspection, the RSDD device is found to be in a non-functional state, the date and findings are to be conspicuously documented in the elevator machine room or controller location.

If upon inspection by Cal/OSHA, the RSDD is found to be non-functional or removed, and the required documentation is not in place, the elevator will be removed from service. If the device is removed to facilitate belt replacement, it must be properly installed and functional before the elevator is returned to service.

(B) On or before November 21 2021, and thereafter, the above specified and documented RSDD shall be installed and operational on the subject elevator.

(C) A successful functionality test of each RSDD shall be conducted once a year, and a copy of completed testing documentation conspicuously located in the machine room or within proximity of the controller.